

No: /2021 /NK/TVPM

Office of the Nirmithi Kendra,
B Block, 4th Floor, Civil Station,
Kudappanakunnu, Thiruvananthapuram 43.
Pmnirmithi01@gmail.com, 0471-2732929
16.07.2021

TENDER NOTICE

The Project Manager, District Nirmithi Kendra, Thiruvananthapuram invites sealed tender from the competent firms/experienced contractors in prescribed form for Providing Oxygen pipe Line Bridge at General Hospital Thiruvananthapuram (Plant to ward 11)

Sl No	PARTICULARS	QTY	UNIT
1	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil	2.55	cum
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m.	4.5	sqm
3	Steel work in built up G I tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete	2387	kg
4	Steel work for purlin/single section with G I pipes including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete	720	kg
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 nominal size)	0.301	cum
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	1.823	cum
7	Centering and shuttering including strutting, etc. and removal of form for: Foundations, footings, bases of columns, etc for mass concrete	437.5	sqm

2) **Bid Price**

- The contract shall be for the full quantity as described above. Corrections if any shall be made by crossing out re-writing with initial and date.
- The rate should be all inclusive of taxes, levies, transports etc.
- Usual deduction of taxes will be made from the gross amount of bill.
- The rate quoted by the bidder shall be fixed for the duration of the contract and shall not be subject to adjustment on any account.

- e) The price should be quoted in Indian rupees only.
- 3) Each bidder shall submit only one tender.
- 4) Validity of tender
- Tender shall remain valid for a period not less than 45 days after the dead line date specified for submission
- 5) Evaluation of tender
- The purchaser will evaluate and compare the tenders determined to be substantially responsive i.e., which
- a) Are properly signed
 - b) Confirm to the terms and conditions and specification.
- 6) Award of Contract
- a) The purchaser will award the contract to the bidder whose tenders has been determined to be substantially responsive and who has offered the lowest evaluated tender price
 - b) Notwithstanding above, the purchaser reserves the right to accept or reject any tenders and to cancel the bidding process and reject all quotations at anytime prior to the award of the contract
 - c) The bidder whose bid is accepted will be notified of the award of the contract by the purchaser prior to expiration of the tender validity period. The terms of the accepted offer shall be incorporated in the purchase order.
- 7) The amount will be released after verification of the material in physical, quality and receipt of invoice in this office according to the availability of funds. Individual or Authorized dealers/agents are only eligible.
- 8) You are requested to provide your offer latest by 12 hours on **22.07.2021** and the tender will be opened at **22.07.2021**.

We look forward to receiving your tenders and thank for your interest in this work.

62
16/07/2021

Project Manager

DISTRICT NIRMITHI KENDRA, THIRUVANANTHAPURAM

TENDERS SCHEDULE

SI No	PARTICULARS	QTY	UNIT	RATE	AMOUNT
1	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.All kinds of soil	2.55	cum		
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m.	4.5	sqm		
3	Steel work in built up G I tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting,fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete	2387	kg		
4	Steel work for purlin/single section with G I pipes including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete	720	kg		
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 nominal size)	0.301	cum		
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mmnominal size)	1.823	cum		
7	Centering and shuttering including strutting, etc. and removal of form for:Foundations, footings, bases of columns, etc for mass concrete	437.5	sqm		
	TOTAL				

Gross Total Cost:- Rs.....
.....(In words) We agree to supply the above goods in accordance with the technical Specification for a total price of Rs.....(amount in figure)(amount in words) with in the period specified in the invitation for quotation.

Signature of Quotationer