

Quotation notice for the toilet construction at Nedumangad Taluk Office

District Nirmithi Kendra invites Competitive quotations from authorized Suppliers/ Experienced individual in the form attached herewith for toilet construction at Nedumangad Taluk Office Thiruvananthapuram.

S.No.	PARTICULARS	QTY	UNIT
1	Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-Charge. In cement morta	0.2	m ³
2	Dismantling aluminium / Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable surplus material and stacking of serviceable material with in 50 metres lead as directed by Engineer - in-Charge	1.65	m ²
3	Hollow block masonry using pre cast solid blocks (Factory made) of size 40x20x10cm or nearest available size confirming to IS 2185 part I of 1979 for Super structure above floor two level upto floor five level for 10cm thick wall in : CM 1:6 (1 cement : 6 coarse sand) including cost of scaffolding etc complete	1	m ³
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 nominal size)	0.396	m ³
5	Reinforced cement concrete work in beams, suspended floors, roofs, having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases up to floor five level excluding the cost of centering, shuttering, finishing and reinforcement, with 1:1.5:3 (1 cement : 1.5 coarse sand (Zone III) : 3 graded stone aggregate 20 mm nominal size).	0.33	m ³
6	Centering and shuttering including strutting, etc. and removal of form for: Suspended floors, roofs, landings, balconies and access platform	2.56	m ²
7	Centering and shuttering including strutting, etc. and removal of form for:	1.74	m ²

	Lintels, beams, plinth beams, girders bressumers and cantilever		
8	Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Thermo - Mechanically Treated bars of grade Fe-500D or more	23.1	kg
9	12 mm cement plaster finished with a floating coat of neat cement of mix: 1:3 (1 cement : 3 fine sand)	4.54	m ²
10	12 mm cement plaster finished with a floating coat of neat cement of mix: 1:4 (1 cement : 4 fine sand)	15.66	m ²
11	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface: Water thinnable cement primer	20.2	m ²
12	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade: Two or more coats on new work	20.2	m ²
13	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work	0.54	m ²
14	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS : 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer -in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3 kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	13.34	m ²
15	Providing and laying Antiskid ceramic floor tiles 400x400 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS :15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4Coarse sand) including pointing the joints with white cement and matching pigment etc., complete.	1.98	m ²
16	Providing and fixing PVC door frame and shutter (for WC and bathroom door shutter size 80X 210	1	LS
17	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately), using good quality Anjili wood /jack wood	0.02	m ³
18	Providing & fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows all complete with :4.0 mm thick glass panes	0.54	m ²

19	Providing and fixing M.S. Grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to steel windows by welding	8.64	kg
----	--	------	----

2) Bid Price

- The contract shall be for the full quantity as described above. Corrections if any shall be made by crossing out re-writing with initial and date.
- The rate should be all inclusive of taxes, levies, transports etc. Unloading shall be done by District Nirmithikendra.
- Usual deduction of taxes will be made from the gross amount of bill.
- The rate quoted by the bidder shall be fixed for the duration of the contract and shall not be subject to adjustment on any account.
- The price should be quoted in Indian rupees only.

3) Each bidder shall submit only one quotation.

4) Validity of quotation

Quotation shall remain valid for a period not less than 45 days after the dead line date specified for submission

5) Evaluation of quotation

The purchaser will evaluate and compare the quotations determined to be substantially responsive ie which

- Are properly signed
- Confirm to the terms and conditions and specification.

6) Award of Contract

- The purchaser will award the contract to the bidder whose quotations has been determined to be substantially responsive and who has offered the lowest evaluated quotation price
- Notwithstanding above, the purchaser reserves the right to accept or reject any quotations and to cancel the bidding process and reject all quotations at any time prior to the award of the contract
- The bidder whose bid is accepted will be notified of the award of the contract by the purchaser prior to expiration of the quotation validity period. The terms of the accepted offer shall be incorporated in the purchase order.

7) The amount will be released after verification of the material in physical ,quality and receipt of invoice in this office according to the availability of funds.Individual or authorized dealers/agents are only eligible.

8) You are requested to provide your offer latest by 12 hours on **26.07.2021** and the quotation will be opened at **26.07.2021**.

We look forward to receiving your quotations and thank for your interest in this work.



Project Manager



Foramat of Quotation

S.No.	PARTICULARS	QTY	UNIT	Amount in figures	Amount in words
1	Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-Charge. In cement morta	0.2	m ³		
2	Dismantling aluminium / Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable surplus material and stacking of serviceable material with in 50 metres lead as directed by Engineer - in-Charge	1.65	m ²		
3	Hollow block masonry using pre cast solid blocks (Factory made) of size 40x20x10cm or nearest available size confirming to IS 2185 part I of 1979 for Super structure above floor two level upto floor five level for 10cm thick wall in : CM 1:6 (1 cement : 6 coarse sand) including cost of scaffolding etc complete	1	m ³		
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 nominal size)	0.39 6	m ³		
5	Reinforced cement concrete work in beams, suspended floors, roofs, having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases up to floor five level excluding the cost of centering, shuttering, finishing and reinforcement, with 1:1.5:3 (1 cement : 1.5 coarse sand (Zone III) : 3 graded stone aggregate 20 mm nominal size).	0.33	m ³		
6	Centering and shuttering including strutting, etc. and removal of form for: Suspended floors, roofs, landings, balconies and access platform	2.56	m ²		
7	Centering and shuttering including strutting, etc. and removal of form for: Lintels, beams, plinth beams, girders bressumers and cantilever	1.74	m ²		
8	Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in	23.1	kg		

	position and binding all complete upto plinth level Thermo - Mechanically Treated bars of grade Fe-500D or more				
9	12 mm cement plaster finished with a floating coat of neat cement of mix: 1:3 (1 cement : 3 fine sand)	4.54	m ²		
10	12 mm cement plaster finished with a floating coat of neat cement of mix: 1:4 (1 cement : 4 fine sand)	15.6 6	m ²		
11	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface: Water thinnable cement primer	20.2	m ²		
12	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade: Two or more coats on new work	20.2	m ²		
13	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work	0.54	m ²		
14	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS : 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer -in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3 kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	13.3 4	m ²		
15	Providing and laying Antiskid ceramic floor tiles 400x400 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS :15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4Coarse sand) including pointing the joints with white cement and matching pigment etc., complete.	1.98	m ²		
16	Providing and fixing PVC door frame and shutter (for WC and bathroom door shutter size 80X 210	1	LS		

17	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately), using good quality Anjili wood /jack wood	0.02	m ³		
18	Providing & fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows all complete with :4.0 mm thick glass panes	0.54	m ²		
19	Providing and fixing M.S. Grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to steel windows by welding	8.64	kg		
	TOTAL				

Gross Total Cost: - Rs.....

(In words) We agree to supply the above goods in accordance with the technical Specification for a total price of Rs.....(amount in figure).....(amount in words) with in the period specified in the invitation for quotation.

Signature of Supplier

