

No: 1360-3/2021/NK/TVPM

Office of the Nirmithi Kendra,  
B Block, 4th Floor, Civil Station,  
Kudappanakunnu, Thiruvananthapuram 43.  
Pmnirmithi01@gmail.com, 0471-2732929  
26.07.2021

**Quotation Notice for Civil Works-04**

District Nirmithi Kendra invites Competitive quotations from authorized Suppliers/Experienced Individual in the form attached herewith for Civil works in District Nirmithi Kendra's Project site at Upgradation of Subcentre at Puthusserimukku.

Sl no	Item	Unit	Qty
1	Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-Charge. In cement mortar	Labour	
2	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil	Cum	0.77
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 nominal size)	Cum	0.63
4	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level:1:1:5:3 (1 cement 1.5 coarse sand :3 graded stone aggregate 20 mm nominal size	Cum	0.94
5	Hollow block masonry using pre cast blocks ( Factory made) of size 40x20x15cm or nearest available size confirming to IS 2185 part 1 of 1979 for super structure up to floor two level with thickness 15cm in: CM 1:6 ( 1 cement : 6 coarse sand ) etc complete	Cum	5.2
6	12 mm cement plaster of mix:1:6 (1 cement : 6 fine sand).	Sqm	71.7
7	Finishing walls with Acrylic Smooth exterior paint of required shade: New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	Sqm	328
8	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work	Sqm	13.56



9	White washing with lime to give an even shade New work (three or more coats)	Sqm	71.68
---	--	-----	-------

## 2) Bid Price

- k) The contract shall be for the full quantity as described above. Corrections if any shall be made by crossing out re-writing with initial and date.
  - l) The rate should be all inclusive of taxes, levies, transports etc.
  - m) Usual deduction of taxes will be made from the gross amount of bill.
  - n) The rate quoted by the bidder shall be fixed for the duration of the contract and shall not be subject to adjustment on any account.
  - o) The price should be quoted in Indian rupees only.
- 3) Each bidder shall submit only one quotation.

### 4) Validity of quotation

Quotation shall remain valid for a period not less than 45 days after the dead line date specified for submission

### 5) Evaluation of quotation

The purchaser will evaluate and compare the quotations determined to be substantially responsive i.e., which

- e) Are properly signed
- f) Confirm to the terms and conditions and specification.

### 6) Award of Contract

a) The purchaser will award the contract to the bidder whose quotations has been determined to be substantially responsive and who has offered the lowest evaluated quotation price

- f) Notwithstanding above, the purchaser reserves the right to accept or reject any quotations and to cancel the bidding process and reject all quotations at anytime prior to the award of the contract
- g) The bidder whose bid is accepted will be notified of the award of the contract by the purchaser prior to expiration of the quotation validity period. The terms of the accepted offer shall be incorporated in the purchase order.

7) The amount will be released after verification of the material in physical, quality and receipt of invoice in this office according to the availability of funds. Individual or Authorized dealers/agents are only eligible.

8) You are requested to provide your offer latest by 12 hours on **02.08.2021** and the Quotation will be opened at **02.08.2021**.

We look forward to receiving your quotations and thank for your interest in this work.

Copy to: 1. Website

2. Notice board

  
Project Manager

**Format of Quotation**

S.N o.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
1	Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-Charge. In cement mortar	Labour			
2	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil	Cum	0.77		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 nominal size)	Cum	0.63		
4	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level:1:1.5:3 (1 cement 1.5 coarse sand :3 graded stone aggregate 20 mm nominal size	Cum	0.94		
5	Hollow block masonry using pre cast blocks ( Factory made) of size 40x20x15cm or nearest available size confirming to IS 2185 part 1 of 1979 for super structure up to floor two level with thickness 15cm in: CM 1:6 ( 1 cement : 6 coarse sand ) etc complete	Cum	5.2		
6	12 mm cement plaster of mix:1:6 (1 cement : 6 fine sand).	Sqm	71.7		



7	Finishing walls with Acrylic Smooth exterior paint of required shade: New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	Sqm	328		
8	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work	Sqm	13.56		
9	White washing with lime to give an even shade: New work (three or more coats)	Sqm	71.68		

Gross Total Cost: - Rs.....

(In words) We agree to supply the above goods in accordance with the technical Specification for a total price of Rs.....(amount in figure).....(amount in words) with in the period specified in the invitation for quotation.

**Signature of Quotationer**