

No: 1838/2021/NK/TVPM

Office of the Nirmithi Kendra,  
B Block, 4th Floor, Civil Station,  
Kudappanakunnu, Thiruvananthapuram 43.  
Pmnirmithi01@gmail.com, 0471-2732929  
27/07/2021

**Quotation notice for Interior Works**

District Nirmithi Kendra invites Competitive Quotation from authorized Suppliers/Individual in the form attached herewith for the work of **Renovation of District Collector's Camp Office Building and other works**


Sl. No.	PARTICULARS	QTY	UNIT
1	Providing and fixing false ceiling at all heights with integral densified calcium sulphate reinforced with fibre and natural filler false ceiling tiles of Size 595x595mm of approved texture, design and patterns having NRC (Noise Reduction coefficient) of 0.50 (minimum) as per IS 8225:1987, Light reflectance of 85%(minimum). Non combustible as per BS:476 (part-4), fire performance as per BS:476 (part 6 & 7), humidity resistance of 100%, thermal conductivity < 0.043W/m K as per ASTM 518:1991, in true horizontal level suspended on interlocking metal T-Grid of hot dipped galvanised iron section of 0.33mm thick (galvanized @ 120 grams per sqm including both sides) comprising of main-T runners of size 24x38 mm of length 3000 mm, cross - T of size 24x32 mm of length 1200 mm and secondary intermediate cross-T of size 24x32 mm of length 600mm to form grid module of size 600 x 600 mm, suspended from ceiling using galvanised mild steel items (galvanizing @ 80 grams per sqm) i.e. 50 mm long, 8 mm outer diameter M-6 dash fasteners, 6 mm dia fully threaded hanger rod upto 1000 mm length and L-shape level adjuster of size 85x25x25x2 mm. Galvanised iron perimeter wall angle of size 24x24x0.40 mm of length 3000 mm to be fixed on periphery wall / partition with the help of plastic rawl plugs at 450 mm center to center and 40 mm long dry wall S. Screws. The work shall be carried out as per specifications, drawing and as per directions of the Engineer-in-Charge. With 15 mm thick tegular edged light weight calcium sulphate false ceiling tiles all works including painting finishes, etc., complete	100	sqm
2	Supplying & Fixing of Over Head storage unit fabricated made of 17mm or nearest Marine plywood Exterior grade for all Storage Top exposed sides, Doors, bottom and all side, inside part shutters with 0.6mm EDGE ponding finish. Back Board of 17mm thk or nearest Marine plywood Exterior grade. Including multipurpose locks and S.S handle and other Necessary Hardwares etc., Standard width of 450 mm	15	sqm



3	Supply ,conveyance ,installation ,testing and commissioning the light fittings of following types made of CRCA sheet 5mm Thick with all accessories and lamps etc ,suspended from ceiling using 2 nos steel chain of length not exceeding 30cm properly hooked to steel hooks anchored to the ceiling and giving connections with required length of 16/0.20mm 3 core copper conductor flex wire conforming to relevent iss or extending the original wiring and giving connection etc.as required		
	i) Supply and Fixing 1 x 18 Watts LED Light Fittings	10	No
	ii) Supply and Laying LED Strip Light	45	mtr
4	Supply ,conveyance ,installation ,testing and commissioning of the Following sizes of exhaust fans in existings opening ,fixing necessary bolt and nuts ,making good the damages etc,as required including giving connections with required length of 24/0.20mm PVC insulated and PVC sheathed 3 core round copper conductor flex conforming to relevent ISS.		
	i) Ceiling rose fan of make Crompton/bajaj/Havelles/orient	4	No
5	Supply and fixing of 2 TN 3 Star Air conditioner Blue Star / Voltas with stabilizer	2	No
6	Modular Kitchen cabinet Unit	24	sqm
7	Outside Signage	1	No
8	Supply and fixing Main Signage	1	No

## 2) Bid Price

- The contract shall be for the full quantity as described above. Corrections if any shall be made by crossing out re-writing with initial and date.
  - The rate should be all inclusive of taxes, levies, transports etc. Usual deduction of taxes will be made from the gross amount of bill.
  - The rate quoted by the bidder shall be fixed for the duration of the contract and shall not be subject to adjustment on any account.
  - The price should be quoted in Indian rupees only.
- 3) Each bidder shall submit only one quotation.



4) Validity of quotation

Tender shall remain valid for a period not less than 45 days after the dead line date specified for submission

5) Evaluation of quotation

The purchaser will evaluate and compare the tenders determined to be substantially responsive ie which

- a) Are properly signed
- b) Confirm to the terms and conditions and specification.

6) Award of Contract

- a) The purchaser will award the contract to the bidder whose quotation has been determined to be substantially responsive and who has offered the lowest evaluated quotation price
- b) Notwithstanding above, the purchaser reserves the right to accept or reject any quotation and to cancel the bidding process and reject all quotation at anytime prior to the award of the contract
- c) The bidder whose bid is accepted will be notified of the award of the contract by the purchaser prior to expiration of the tender validity period. The terms of the accepted offer shall be incorporated in the purchase order.

7) The amount will be released after verification of the material in physical ,quality and receipt of invoice in this office according to the availability of funds. Individual or authorized dealers/agents are only eligible.

8) You are requested to provide your offer latest by 12 hours on **04.08.2021** and the tenders will be opened at **04.08.2021**

We look forward to receiving your quotation and thank for your interest in this work.

  
**Project Manager**

Copy to: 1. Website

2. Notice board





### Format of Quotation

Sl No	Description	Quantity	Unit	Rate	AMOUNT	
					Amount in figures	Amount in words
1	Providing and fixing false ceiling at all heights with integral densified calcium sulphate reinforced with fibre and natural filler false ceiling tiles of Size 595x595mm of approved texture, design and patterns having NRC (Noise Reduction coefficient) of 0.50 (minimum) as per IS 8225:1987, Light reflectance of 85%(minimum). Non combustible as per BS:476 (part-4), fire performance as per BS:476 (part 6 & 7), humidity resistance of 100%, thermal conductivity < 0.043W/m K as per ASTM 518:1991, in true horizontal level suspended on interlocking metal T-Grid of hot dipped galvanised iron section of 0.33mm thick (galvanized @ 120 grams per sqm including both sides) comprising of main-T runners of size 24x38 mm of length 3000 mm, cross - T of size 24x32 mm of length 1200 mm and secondary intermediate cross-T of size 24x32 mm of length 600mm to form grid module of size 600 x 600 mm, suspended from ceiling using galvanised mild steel items (galvanizing @ 80 grams per sqm) i.e. 50 mm long, 8 mm outer diameter M-6 dash fasteners, 6 mm dia fully threaded hanger rod upto 1000 mm length and L-shape level adjuster of size 85x25x25x2 mm. Galvanised iron perimeter wall angle of size 24x24x0.40 mm of length 3000 mm to be fixed on periphery wall / partition with the help of plastic rawl plugs at 450 mm center to center and 40 mm long dry wall S. Screws. The work shall be carried out as per specifications, drawing and as per directions of the Engineer-in-Charge. With 15 mm thick tegular edged light weight calcium sulphate false ceiling tiles all works including painting finishes, etc., complete	100	sqm			
2	Supplying & Fixing of Over Head storage unit fabricated made of 17mm or nearest Marine plywood Exterior grade for all Storage Top exposed sides, Doors, bottom and all side, inside part shutters with 0.6mm EDGE ponding finish. Back Board of 17mm thk or nearest Marine plywood Exterior grade. Including multipurpose locks and S.S handle and other Necessary Hardwares etc., Standard width of	15	sqm			



	450 mm					
3	Supply ,conveyance ,installation ,testing and commissioning the light fittings of following types made of CRCA sheet.5mm Thick with all accessories and lamps etc.,suspended from ceiling using 2 nos steel chain of length not exceeding 30cm properly hooked to steel hooks anchored to the ceiling and giving connections with required length of 16/0.20mm 3 core copper conductor flex wire conforming to relevent iss or extending the original wiring and giving connection etc.as required					
	iii) Supply and Fixing 1 x 18 Watts LED Light Fittings	10	No			
	iv) Supply and Laying LED Strip Light	45	mtr			
4	Supply ,conveyance ,installation ,testing and commissioning of the Following sizes of exhaust fans in existings opening ,fixing necessary bolt and nuts ,making good the damages etc,as required including giving connections with required length of 24/0.20mm PVC insulated and PVC sheathed 3 core round copper conductor flex conforming to relevent ISS.					
	ii) Ceiling rose fan of make Crompton/bajaj/Havelles/orient	4	No			
5	Supply and fixing of 2 TN 3 Star Air conditioner Blue Star / Voltas with stabilizer	2	No			
6	Modular Kitchen cabinet Unit	24	sqm			
7	Outside Signage	1	Nos			
8	Supply and fixing Main Signage	1	Nos			

Gross Total Cost: - Rs.....

(In words) We agree to supply the above goods in accordance with the technical Specification for a total price of Rs.....(amount in figure).....(amount in words) with in the period specified in the invitation for quotation.

**Signature of Quotationer**