

No: 1810/2021/NK/TVPM

Office of the Nirmithi Kendra,
B Block, 4th Floor, Civil Station,
Kudappanakunnu, Thiruvananthapuram 43.
Pmnirmithi01@gmail.com, 0471-2732929
13/09/2021

Quotation notice for Roofing Works

District Nirmithi Kendra invites Competitive quotations from authorized Firms/Contractors in the form attached herewith for roof works at Sub center Pallithura.

S.No.	PARTICULARS	QTY	UNIT
1	Providing Trafford Aluminium sheet roofing including vertical/ curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal / vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 1.00 mm thick with zinc coating not less than 275 gm./m ²	45	SQM
2	Providing and fixing false ceiling with 7.5 mm thick PVC wooden grains panel board ceiling of approved quality in aluminium frame work with necessary screws etc complete (aluminium frame work shall be paid separately)	45	SQM
3	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	291.140	Kg
4	Providing and fixing full height ceiling board with 7.5 mm thick PVC plain panel board ceiling of approved quality in aluminium frame work with necessary screws etc complete (aluminium frame work shall be paid separately)	45	SQM

5	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. for post.	2.179	cum
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 nominal size)	0.571	cum
7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:2:4 (cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	0.289	cum
	Total		

2) Bid Price

- The contract shall be for the full quantity as described above. Corrections if any shall be made by crossing out re-writing with initial and date.
- The rate should be all inclusive of taxes, levies, transports etc.
- Usual deduction of taxes will be made from the gross amount of bill.
- The rate quoted by the bidder shall be fixed for the duration of the contract and shall not be subject to adjustment on any account.
- The price should be quoted in Indian rupees only.

3) Each bidder shall submit only one quotation.

4) Validity of quotation

.Quotation shall remain valid for a period not less than 30 days after the dead line date specified for submission

5) Evaluation of quotation

The purchaser will evaluate and compare the quotations determined to be substantially responsive ie which

- Are properly signed and as per the format published.
- Confirm to the terms and conditions and specification.

6) Award of Contract

- a) The purchaser will award the contract to the bidder whose quotations has been determined to be substantially responsive and who has offered the lowest evaluated quotation rate
 - b) Notwithstanding above, the purchaser reserves the right to accept or reject any quotations and to cancel the bidding process and reject all quotations at anytime prior to the award of the contract
 - c) As it is an emergency work, the quotationer shall assure the completion of works within the time frame. The period of completion of the works shall be ten days.
 - d) The bidder whose bid is accepted will be notified of the award of the contract by the purchaser prior to expiration of the quotation validity period.
The terms of the accepted offer shall be incorporated in the work order.
- 7) The amount will be released after verification of the works in physical ,quality and receipt of invoice in this office according to the availability of funds.
- 8) You are requested to provide your offer latest by 12 hours on **18.09.2021** and the quotation will be opened at **18.09.2021** at 3pm

We look forward to receiving your quotations and thank for your interest in this work.

Project Manager

Copy to - Notice board and website

Quotation Format

S.No.	PARTICULARS	QTY	UNIT	Amount
1	Providing Trafford Aluminium sheet roofing including vertical/ curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal / vertical or curved surfaces), excluding the cost of purling, rafters and trusses and including cutting to size and shape wherever required. 1.00 mm thick with zinc coating not less than 275 gm/m ²	45	SQM	
2	Providing and fixing false ceiling with 7.5 mm thick PVC wooden grains panel board ceiling of approved quality in aluminium frame work with necessary screws etc complete (aluminium frame work shall be paid separately)	45	SQM	
3	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	291.140	Kg	
4	Providing and fixing full height ceiling board with 7.5 mm thick PVC plain panel board ceiling of approved quality in aluminium frame work with necessary screws etc complete (aluminium frame work shall be paid separately)	45	SQM	
5	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.	2.179	cum	
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 nominal size)	0.571	cum	

7	Painting G.I pipes and fittings with synthetic enamel white paint with two coats over a ready mixed priming coat, both of approved quality for new work: 20 mm diameter pipe	0.289	cum	
8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:2:4 (cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	45	SQM	
	Total			

Gross Total Cost: - Rs.....

(In words) We agree to supply the above goods in accordance with the technical Specification for a total price of Rs.....(amount in figure).....(amount in words) with in the period specified in the invitation for quotation.

Signature of Contractor