

Quotation for Second Stage Furnishing of State Food Commission Pattom Thiruvananthapuram

Sl. No.	Particulars	Qty	Unit	Rate	Amount
A	Infrastructure Facilities				
1	Solid Wood Wall Mounted Foldable Dining Table Dimensions: H 59 x W 43 x D 5; (all dimensions in inches)	3	No.s		
2	Sofa set five seater				
	Solid Wood Sofa cum BedSofa : H 33 x W 65 x D 33.5; Seating Height - 14.7; Bed : H 33 x W 65 x D 60.2; Seating Height - 14.7(all dimensions in inches)Specifications : Primary Material : Sheesham Wood/Equivalent Secondary Material : MDF 12MM Fabric : Cotton Matty	7	No.s		
3	L-shaped Sofa set for Chairman				
	L Shape Sofa Set in Leatherette (Black) PRODUCT DIMENSIONS- L-88, D-55, H-31 Ottoman- L-23, D-23, H-31 (Inches) :- COLOR- Black PRIMARY MATERIAL- Solid Wood & 32 density Supersoft Air Foam UPHOLSTERY MATERIAL- Premium Fabric :- SEATING CAPACITY- 5 seater	1	No.s		
4	Normal Sofa Set for Lobby				
	Wooden (Sheesham/Equivalent)Sofa Set with Cushion Fabric 3 Seater Upholestry: Cotton Filling Material: Cotton W x H x D: 173.99 cm x 84.9 cm x 63.5 cm (5 ft 8 in x 2 ft 9 in x 2 ft 1 in)	2	No.s		
5	Wooden panelling at existing walls for Office of Commission				
	Supply & installation of wall panelling made of pinewood E1 grade fiberboard,melamine/veneer laminated finish, groove perforated L32-2 - (2mm grooves @32mm centers), backlined with Sound texblack acoustical fleece, tongue-groove edge for a seamless look, 5-test fire retardant grade/ Non FR, Acoustics NRC 0.65- 0.75 (For E300* Mounting), size 128x2440x12mm, volume density of baseboard 800 - 830 Kg/m3, 10-10.5Kgs/m2 (L32), installed by using Strutframework system. Slats to be backed with Synthethik PF 10x25 adhered to wall with stick .The Panneling shall be finished as per the drawings and to thesatisfaction of the Engineer in Charge. All the support system shall be as per theApproved make list and the suspension system shall be got approved before starting installation at site.	41.075	m2		
6	Supply of Excutive Highback Revolving Chair Key Features: Mesh back with Adjustable Lumbar Support. Fabric Upholstered seat with Moulded Foam. Synchro Single Locking Mechanism. Adjustable Armrest (Up-Down) Adjustable Headrest(Can Adjust Movement) Chrome Base with Smooth Nylon Castor. Made with all BIFMA standard High Back Modern Style	3	No.s		
7	Black Fabric & Foam Medium Back Visitor Chair with Arms	10	No.s		
8	Solid Bench of Size 1120mm(l) x 375mm (w) x 470m (ht)	3	No.s		

9	Providing Glass Door Office Almirah Squardro type using powder coated steel almirah,all area exposed side area with suitable approved colour 1mm thick of size 2.1 x .45mlaminate finish including lock,handle,hinges etc complete	7	No.s		
10	Office inside name signage supply and fixing charge size : 30 x 15	12	No.s		
11	Main signage board out side. size: 600 x 200 with LED lightings with panelling Including Charge of hoisting ,Scaffolding etc charges complete at 5th floor	1	No.s		
12	Providing and fixing Wall Mounted bracket for signage boards	13	No.s		
13	Aluminium Door with glass panes of thickness 4mm of size 1.2*2.1m	1	No.s		
14	Heavy Duty Door closer for existing doors with neccessary fittings ,installation charge etc complete	18	No.s		
15	Supplying 75mm thick Modular partitions The frames are made out of powder coated approved shade aluminium sections with float glass panes of 4.0 mm thickness . 9mm thickness pre-laminated particle board tiles of approved shade fixed at the partitions as per the design and drawings bottom of the partition fixed with the single race way used for wiring purpose with end caps and hardwares,provision for electrical cable tray below workstations including cost of all materials,transportation,labour charges,loading and unloading etc..complete	11.701	m2		
16	Providing and fixing 18 mm thick gang saw cut, mirror, polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations, of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels.Granite of any colour and shadeArea of slab upto 0.50 sqm	6.93	sqm		
17	Curtain Fabric available with thick fabric linings to suit the specific requirement with differing degree of light absorption and heat insulating qualities. Available in different color combinations, modern and ethnic style with neccessary fittings etc complete as per direction of engineer in charge	83.5	m		
18	Water Purifier of Capacity upto 10L with Smart Plus (RO+UV+MTDS) (Bluestar/Aquagaurd /Equivalent)				
19	Supplying of blue star/ Equivalent make 1.5 Ton Inverter Split AC (3 star)				
20	Supply of voltage stabilizer				
21	Supply of drain pipe for AC				
22	Supply of outdoor support for AC				
23	Providing and fixing of copper pipe for AC make 1.5 Ton split 1 airconditioner (3 star)				



2	Electrical Works at 5th Floor				
1	LIGHT / FAN WIRING				
	Light /Fan point wiring with 2 Run '1.5 sqmm Finolex PVC insulated copper conductor to be laid in 2mm suitable PVC conduit with Bend,Couplings, etc.. And fixing with PVC clamps screws etc.All conduits to be laid above the conduit with Bend,Couplings, etc.. And fixing with false ceiling/partition/concealed in the wall 6A Modular type etc. plate and metal Box or PVC Box Wiring to be connected with supply & fixing of switch (MI(ROMA/CRABTREE) with suitable Modular switches				
a	One light Controlled by One Switch	7	Pts		
b	6A plug points 5 pin type (combination in position)	7	Pts		
c	6 A plug points 5 pin type (independent position)	7	Pts		
2	CIRCUIT WIRING				
	Supply & Wiring with Flame Retardant Insulated PVC copper wire as per grade IS 994 for Circuits,Computer point,Power points within 2mm thk PVC conduits with necessary accessories and with proper clamps and to be concealed below the false ceiling It comprises as follows:-				
a	3Run of 2.5Sqmm copper wire in PVC Conduit for Power points	80	Mtr		
3	POWER POINT OUTLETS				
c	Supply & Installation of 1Nos of 16A Socket controlled by 1No 16A Switch with front plate with enclosure and other accessories etc., (Printer, Counting, Data Hub & AC Points) (MK/ROMA/CRABTREE)	4	Set		
d	25A Metal clad socket for AC Point	4	Set		
3	NETWORKS				
1	Supplying and laying of Cat-6 E UTP cable in the existing PVC rigid pipe/race way cable tray including numbering for both end complete connection testing etc. as required	160	Mtr		

[illegible]