

No:1136/E1/2020/NK/TVPM

Office of the Nirmithi Kendra,
B Block, 4th Floor, Civil Station,
Kudappanakunnu, Thiruvananthapuram 43.
Pmnirmithi01@gmail.com, 0471-2732929
18/10/2021

Tender notice for Retaining wall work at Parandakuzhi Colony

District Nirmithi Kendra invites Competitive Tenders from authorized Suppliers/Individual in the form attached herewith for the work of **Retaining wall work at Parandakuzhi Colony.**

Sl. No.	PARTICULARS	QTY	UNIT
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed. Ordinary rock	130.49	Cum
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 nominal size.	11.00	Cum
3	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m.	19.98	Cum
4	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement All work up to plinth level: 1:1:5:3 (1 cement 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size	27.56	Cum
5	Reinforced cement concrete work in walls (any	49.95	Cum

Delivered
30

	thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. up to floor five level excluding cost of centering, shuttering, finishing and reinforcement :1:1.5:3(1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)		
6	Centering and shuttering including strutting, etc. and removal of form for: Walls (any thickness) including attached pilasters, butteresses, plinth and string courses etc.	716.51	Sqm

2) Bid Price

- The contract shall be for the full quantity as described above. Corrections if any shall be made by crossing out re-writing with initial and date.
- The rate should be all inclusive of taxes, levies, transports etc. Usual deduction of taxes will be made from the gross amount of bill.
- The rate quoted by the bidder shall be fixed for the duration of the contract and shall not be subject to adjustment on any account.
- The price should be quoted in Indian rupees only.

3) Each bidder shall submit only one tender.

4) Validity of tender

Tender shall remain valid for a period not less than 45 days after the dead line date specified for submission

5) Evaluation of tender

The purchaser will evaluate and compare the tenders determined to be substantially responsive ie which

- Are properly signed
- Confirm to the terms and conditions and specification.

6) Award of Contract

- The purchaser will award the contract to the bidder whose tenders has

Delius
(16)

been determined to be substantially responsive and who has offered the lowest evaluated tender price

- b) Notwithstanding above, the purchaser reserves the right to accept or reject any tenders and to cancel the bidding process and reject all tenders at any time prior to the award of the contract
 - c) The bidder whose bid is accepted will be notified of the award of the contract by the purchaser prior to expiration of the tender validity period. The terms of the accepted offer shall be incorporated in the purchase order.
- 7) The amount will be released after verification of the material in physical, quality and receipt of invoice in this office according to the availability of funds. Individual or authorized dealers/agents are only eligible.
- 8) You are requested to provide your offer latest by 12 hours on **28.10.2021** and the tenders will be opened at **28.10.2021 3pm**

We look forward to receiving your tenders and thank for your interest in this work.


Project Manager

Format of Tender

Sl No	Description	Quantity	Unit	Rate	AMOUNT	
					Amount in figures	Amount in words
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed. Ordinary rock	130.49	Cum			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 nominal size.	11.00	Cum			
3	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m.	19.98	Cum			
4	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement All work up to plinth level: 1:1:5:3 (1 cement 1.5 coarse sand : 3 graded stone aggregate 20 mm	27.56	Cum			

	nominal size					
5	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. up to floor five level excluding cost of centering, shuttering, finishing and reinforcement :1:1.5:3(1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	49.95	Cum			
6	Centering and shuttering including strutting, etc. and removal of form for:Walls (any thickness) including attached pilasters, butteresses, plinth and string courses etc.	716.51	Sqm			

Gross Total Cost: - Rs.....

(In words) We agree to supply the above goods in accordance with the technical Specification for a total price of Rs.....(amount in figure).....(amount in words) with in the period specified in the invitation for tender.

Signature of Supplier