

Tender notice for Interior work

District Nirmithi Kendra invites Competitive ^{tender} quotations from authorized Suppliers/Individual in the form attached herewith for Interior work District nirmithi kendra's Project site at setting up of Taluk supply office, Kadakampalli.

S.No.	PARTICULARS	QTY	UNIT
1	Supplying 75mm thick Modular partitions with frames are made out of powder coated approved shade aluminium sections with 9mm thickness pre-laminated particle board tiles of approved shade fixed at the partitions as per the design and drawings bottom of the partition fixed with the single race way used for wiring purpose with end caps and hardwares, provision for electrical cable tray including cost of all materials, transportation, labour charges, loading and unloading etc., complete	42.600	sqm
2	Wooden Wall Paneling (Reception area) Supplying, providing and fixing in position Wooden wall panelling using with 19 mm thick marine plywood on the finished face and finished with 1mm lamination approved brand and shade as in the design drawing including cost conveyance of all materials, labour charges loading and unloading etc. complete.	44.801	Sqm
3	Providing & Fixing of Gypsum Parition using Framework for 70mm Stud(0.5mm Thick Flange of 34mm and other Flange of 36mm made of GI steel) Placed at 600mm Center to Center in 72mm Floor and Ceiling Channel.(0.5mm thick Flange equal plant of 32mm made of GI steel).It is anchored to the floor and ture Ceiling into suitable anger Fastners or metal Screws with Nylon Plug 12.5mm Thick Gypsum board are to be fixed to the frame work with joints staggerd avoid leakage to Joints. Existing GI Frame work using Star screw every 300mm center to center.Partition door area all around for inside the frame using Hard wood. The Partition inside 25mm glass wool the Part inside using 25mm Thick glass wool of density of 16kg per m3 shall we based in the Kavity. Finally square and paper edge of	24.4	sqm

	the post or to be joined and finished so as to have a fresh look includes Beading and finishing Gyp work Jointing Compound gypwork jointing Paper Tape and one coat of try wall Top Coat. if Necessary Area 5mm plain glass are Fixed .		
4	Supply and Installation of 1 ton Inverter split type 1 phase A/C including inbuilt stabilizer , outdoor unit clamp and accessories with following items. (make-Mitsubishi/Daikin/LG/equivalent) 1] Hard drawn copper refrigerant piping with insulation- 3 mtr 2] Electrical cable b/w Indoor and outdoor units.- 3 mtr 3] Insulated drain pipes - 3 mtr	2	no
5	Supply and Installation of 2 ton Inverter split type 1 phase A/C including inbuilt stabilizer, outdoor unit clamp and accessories with following items. (make-Mitsubishi/daikin/LG/equivalent) 1] Hard drawn copper refrigerant piping with insulation- 3 mtr 2] Electrical cable b/w Indoor and outdoor units- 3 mtr 3] Insulated drain pipes - 3 mtr	1	no
6	Providing and fixing 100 mm brass locks (best make of approved quality) for aluminium doors including necessary cutting and making good etc. complete	2	no
7	Providing and fixing Hydraulic door closer bottle type M.S. body with necessary accessories and screws etc complete	2	no
8	supply of 5 Kva Stablizer	3	no
9	Providing and fixing 100mm wide vertical blinds of approved shade and texture to windows with nylon strings for adjustments and with locking arrangements including cost and conveyance of all materials, labour charges etc. complete as per standard specifications and directions of the Engineers	38.431	sqm
10	Providing & fixing false ceiling with 12mm thick Gypsum board fixed to a grid made out of anodised aluminium T sections 35x15x1.5 mm size main runners and cross runners mm fixed to main runners placed 600mm c/c both ways so as to form a grid of 600mm square. Frame work suspended from the ceiling by level adjusting hangers of 6mm dia M.S rods fixed to roof slab by means of ceiling cleats.hangers of 6mm dia suspenders shall be placed 600x1200 mm c/c including fixing to the frame with C.P brass screws complete. Providing and fixing anodised aluminium work consisting of tee/angle sections of approved make conforming to IS :733 in frames of false ceiling	45.250	sqm

	including aluminium angle cleats with necessary C.P brass /stainless steel sunk screws ,aluminium perimeter angles fixed to wall with rawl plugs @ 450mm centre to centre and fixing the frame work to level adjusting hangers with necessary cadmium plated machine screws all complete as per approved architectural drawings and direction of the Engineer-in-charge.The board is finished with filling the tapered edges of the board with joining compound etc, Details of cost for 216.14 sqm Consider a shed of 20x10 metres. (External dimensions of plinth). Area of roof- 20.2x10.70m = 216.14 sqm		
11	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade:Two or more coats on new work	96.000	sqm
12	Office Inside Name Signage Supply and fixing charge	10	no
13	Outside Signage	2	no

2) Bid Price

- The contract shall be for the full quantity as described above. Corrections if any shall be made by crossing out re-writing with initial and date.
- The rate should be all inclusive of taxes, levies, transports, Unloading etc.
- Usual deduction of taxes will be made from the gross amount of bill.
- The rate quoted by the bidder shall be fixed for the duration of the contract and shall not be subject to adjustment on any account.
- The price should be quoted in Indian rupees only.

3) Each bidder shall submit only one quotation.

4) Validity of quotation

Quotation shall remain valid for a period not less than 45 days after the dead line date specified for submission

5) Evaluation of quotation

The purchaser will evaluate and compare the quotations determined to be substantially responsive ie which

- Are properly signed
- Confirm to the terms and conditions and specification.

6) Award of Contract

- The purchaser will award the contract to the bidder whose quotations has been determined to be substantially responsive and who has offered the

lowest evaluated quotation price

- b) Notwithstanding above, the purchaser reserves the right to accept or reject any quotations and to cancel the bidding process and reject all quotations at any time prior to the award of the contract
- c) The bidder whose bid is accepted will be notified of the award of the contract by the purchaser prior to expiration of the quotation validity period.

The terms of the accepted offer shall be incorporated in the purchase order.

- 7) The amount will be released after verification of the material in physical ,quality and receipt of invoice in this office according to the availability of funds. Individual or authorized dealers/agents are only eligible.
- 8) You are requested to provide your offer latest by 12 hours on **22.11.2021** and the quotation will be opened at **22.11.2021**.

We look forward to receiving your quotations and thank for your interest in this work.


Project Manager

Format of Tender

S.No.	PARTICULARS	QTY	UNIT
1	Supplying 75mm thick Modular partitions with frames are made out of powder coated approved shade aluminium sections with 9mm thickness pre-laminated particle board tiles of approved shade fixed at the partitions as per the design and drawings bottom of the partition fixed with the single race way used for wiring purpose with end caps and hardwares, provision for electrical cable tray including cost of all materials, transportation, labour charges, loading and unloading etc.,complete	42.600	sqm
2	Wooden Wall Paneling (Reception area) Supplying, providing and fixing in position Wooden wall panelling using with 19 mm thick marine plywood on the finished face and finished with 1mm lamination approved brand and shade as in the design drawing including cost conveyance of all materials, labour charges loading and unloding etc. complete.	44.801	Sqm
3	Providing & Fixing of Gypsum Parition using Framework for 70mm Stud(0.5mm Thick Flange of 34mm and other Flange of 36mm made of GI steel) Placed at 600mm Center to Center in 72mm Floor and Ceiling Channel.(0.5mm thick Flange equal plant of 32mm made of GI steel).It is anchored to the floor and ture Ceiling into suitable anger Fastners or metal Screws with Nylon Plug 12.5mm Thick Gypsum board are to be fixed to the frame work with joints staggerd avoid leakage to Joints. Existing GI Frame work using Star screw every 300mm center to center.Partition door area all around for inside the frame using Hard wood. The Partition inside 25mm glass wool the Part inside using 25mm Thick glass wool of density of 16kg per m3 shall we based in the Kavity. Finally square and paper edge of the post or to be joined and finished so as to have a fresh look includes Beading and finishing Gyp work Jointing Compound gypwork jointing Paper Tape and one coat of try wall Top Coat. if Necessary Area 5mm plain glass are Fixed .	24.4	sqm

4	Supply and Installation of 1 ton Inverter split type 1 phase A/C including inbuilt stabilizer , outdoor unit clamp and accessories with following items. (make-Mitsubishi/Daikin/LG/equivalent) 1] Hard drawn copper refrigerant piping with insulation- 3 mtr 2] Electrical cable b/w Indoor and outdoor units.- 3 mtr 3] Insulated drain pipes - 3 mtr	2	no
5	Supply and Installation of 2 ton Inverter split type 1 phase A/C including inbuilt stabilizer, outdoor unit clamp and accessories with following items. (make-Mitsubishi/daikin/LG/equivalent) 1] Hard drawn copper refrigerant piping with insulation- 3 mtr 2] Electrical cable b/w Indoor and outdoor units- 3 mtr 3] Insulated drain pipes - 3 mtr	1	no
6	Providing and fixing 100 mm brass locks (best make of approved quality) for aluminium doors including necessary cutting and making good etc. complete	2	no
7	Providing and fixing Hydraulic door closer bottle type M.S. body with necessary accessories and screws etc complete	2	no
8	supply of 5 Kva Stablizer	3	no
9	Providing and fixing 100mm wide vertical blinds of approved shade and texture to windows with nylon strings for adjustments and with locking arrangements including cost and conveyance of all materials, labour charges etc. complete as per standard specifications and directions of the Engineers	38.431	sqm
10	Providing & fixing false ceiling with 12mm thick Gypsum board fixed to a grid made out of anodised aluminium T sections 35x15x1.5 mm size main runners and cross runners mm fixed to main runners placed 600mm c/c both ways so as to form a grid of 600mm square. Frame work suspended from the ceiling by level adjusting hangers of 6mm dia M.S rods fixed to roof slab by means of ceiling cleats.hangers of 6mm dia suspenders shall be placed 600x1200 mm c/c including fixing to the frame with C.P brass screws complete. Providing and fixing anodised aluminium work consisting of tee/angle sections of approved make conforming to IS :733 in frames of false ceiling including aluminium angle cleats with necessary C.P brass /stainless steel sunk screws ,aluminium perimeter angles fixed to wall with rawl plugs @ 450mm centre to centre and fixing the frame work to level adjusting hangers with necessary cadmium plated machine screws	45.250	sqm

	all complete as per approved architectural drawings and direction of the Engineer-in-charge. The board is finished with filling the tapered edges of the board with joining compound etc, Details of cost for 216.14 sqm Consider a shed of 20x10 metres. (External dimensions of plinth). Area of roof- 20.2x10.70m = 216.14 sqm		
11	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade: Two or more coats on new work	96.000	sqm
12	Office Inside Name Signage Supply and fixing charge	10	no
13	Outside Signage	2	no

Gross Total Cost: - Rs.....

(In words) We agree to supply the above goods in accordance with the technical Specification for a total price of Rs.....(amount in figure).....(amount in words) with in the period specified in the invitation for quotation.

Signature of Supplier