

QUOTATION NOTICE

District Nirmithi Kendra, Thiruvananthapuram invites sealed quotations from the competent firms/experienced contractors in prescribed form for Electrical works at Upgradation of UPHC Kovalam..

| Sl No | PARTICULARS | QTY | UNIT |
|-------|--|-----|------|
| 1 | Supply and installation of double cover enclosure of 16 Way MCB DB and ELCB for 3 phase inclusive of copper / brass bus bar, neutral link and DIN bar suitable for incorporating MCB 26 nos ELCB 1nos with isolator etc. including providing blanking plates in the blanking slots and fixed in recess including cutting holes on the wall, making good the damages, colour washing etc as required. | 1 | nos |
| 2 | Supply and fixing the following sizes of PVC Conduit conforming to IS 9537 / 1983 part III along with all required accessories in recess including cutting the wall and making good the damages etc as required. | | |
| a | 20 mm pipe with necessary coupling (50nos), bend (60nos), 4way junction (25nos), 3way junction (25nos) and one way (35nos) | 110 | m |
| 3 | Wiring for circuit/ submain wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required. | 15 | Nos |
| a | 2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire | 3 | Coil |
| b | 2 X 1.5 sq. mm + 1 X 1.5 sq. mm earth wire | 4 | Coil |
| c | 2 X 1sq. mm + 1 X 1 sq. mm earth wire | 14 | Coil |
| d | 2 X 4 sq. mm + 1 X 4 sq. mm earth wire | 1 | Coil |
| 4 | Supply, conveyance, installation, testing and commissioning of ceiling fans of the following sizes using standard accessories excluding resistance type regulator, wiring the down rod with 16/0.20mm PVC insulated and PVC sheathed 650/1100V grade 3 core round copper conductor flex wire or with extended original wiring etc. as required. 1200mm sweep -5star rated ceiling fan complete with 300mm down rod, canopies, shackles | 7 | nos |

| | | | |
|----|---|----|-----|
| | and blades and resistance type regulator working on 230V/240V single phase A/C | | |
| 5 | Supplying and fixing following size/ modules, GI / Pvc box alongwith modular base & cover plate for modular switches in recess etc as required.3 Module box | 7 | Nos |
| 6 | Supplying and fixing following size/ modules, GI / Pvc box alongwith modular base & cover plate for modular switches in recess etc as required.6 Module box | 7 | Nos |
| 7 | Supply, installation, testing and commissioning of Bulkhead light fittings with all accessories and giving connections with 16/0.20 mm 3 core PVC insulated and sheathed round copper conductor flex wire or extending the original wiring and giving connections as required. | 10 | Nos |
| 8 | Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.6 pin 15/16 amp socket outlet | 10 | Nos |
| 9 | Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.15/16 amp switch | 10 | Nos |
| 10 | Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.5/6 amps switch | 25 | Nos |
| 11 | Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.15/16 amp switch | 25 | Nos |
| 12 | Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.6 pin 5/6 amp socket outlet | 25 | Nos |

2) Bid Price

- The contract shall be for the full quantity as described above. Corrections if any shall be made by crossing out re-writing with initial and date.
- The rate should be all inclusive of taxes, levies, transports etc.
- Usual deduction of taxes will be made from the gross amount of bill.
- The rate quoted by the bidder shall be fixed for the duration of the contract and shall not be subject to adjustment on any account.
- The price should be quoted in Indian rupees only.

3) Each bidder shall submit only one quotation.

4) Validity of quotation

Quotation shall remain valid for a period not less than 45 days after the dead line date specified for submission

5) Evaluation of quotation

The purchaser will evaluate and compare the quotations determined to be substantially responsive i.e., which

a) Are properly signed

b) Confirm to the terms and conditions and specification.

6) Award of Contract

a) The purchaser will award the contract to the bidder whose quotations has been determined to be substantially responsive and who has offered the lowest evaluated quotation price

b) Not with standing above, the purchaser reserves the right to accept or reject any quotations and to cancel the bidding process and reject all quotations at any time prior to the award of the contract

c) The bidder whose bid is accepted will be notified of the award of the contract by the purchaser prior to expiration of the quotation validity period. The terms of the accepted offer shall be incorporated in the purchase order.

7) The amount will be released after verification of the material in physical, quality and receipt of invoice in this office according to the availability of funds. Individual or Authorized dealers/agents are only eligible.

8) You are requested to provide your offer latest by 12 hours on **06.01.2022** and the Quotation will be opened at **06.01.2022**.

We look forward to receiving your quotations and thank for your interest in this work.




Project Manager

QUOTATION NO.1383/21/DNK

DISTRICT NIRMITHI KENDRA, THIRUVANANTHAPURAM

QUOTATION SCHEDULE

| Sl.NO | PARTICULARS | QTY | UNIT | RATE | AMOUNT |
|-------|--|-----|------|------|--------|
| 1 | Supply and installation of double cover enclosure of 16 Way MCB DB and ELCB for 3 phase inclusive of copper / brass bus bar, neutral link and DIN bar suitable for incorporating MCB 26 nos ELCB 1nos with isolator etc. including providing blanking plates in the blanking slots and fixed in recess including cutting holes on the wall, making good the damages, colour washing etc as required. | 1 | nos | | |
| 2 | Supply and fixing the following sizes of PVC Conduit conforming to IS 9537 / 1983 part III along with all required accessories in recess including cutting the wall and making good the damages etc as required. | | | | |
| a | 20 mm pipe with necessary coupling (50nos),bend(60nos),4way junction(25nos),3way junction(25nos) and one way (35nos) | 110 | m | | |
| 3 | Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required. | 15 | Nos | | |
| a | 2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire | 3 | Coil | | |
| b | 2 X 1.5 sq. mm + 1 X 1.5 sq. mm earth wire | 4 | Coil | | |
| c | 2 X 1sq. mm + 1 X 1 sq. mm earth wire | 14 | Coil | | |
| d | 2 X 4 sq. mm + 1 X 4 sq. mm earth wire | 1 | Coil | | |
| 4 | Supply, conveyance, installation, testing and commissioning of ceiling fans of the following | 7 | nos | | |

| | | | | | |
|----|--|----|-----|--|--|
| | sizes using standard accessories excluding resistance type regulator, wiring the down rod with 16/0.20mm PVC insulated and PVC sheathed 650/1100V grade 3 core round copper conductor flex wire or with extended original wiring etc. as required.1200mm sweep -5star rated ceiling fan complete with 300mm down rod ,canopies, shackeles and blades and resistance type regulator working on 230V/240V single phase A/C | | | | |
| 5 | Supplying and fixing following size/ modules, GI / Pvc box alongwith modular base & cover plate for modularswitches in recess etc as required.3 Module box | 7 | Nos | | |
| 6 | Supplying and fixing following size/ modules, GI / Pvc box alongwith modular base & cover plate for modularswitches in recess etc as required.6 Module box | 7 | Nos | | |
| 7 | Supply, installation, testing and commissioning of Bulkhead light fittings with all accessories and giving connections with 16/0.20 mm 3 core PVC insulated and sheathed round copper conductor flex wire or extending the original wiring and giving connections as required. | 10 | Nos | | |
| 8 | Supplying and fixing following modular switch/ socket on the existing modular plate & switch boxincluding connections but excluding modular plate etc. as required.6 pin 15/16 amp socket outlet | 10 | Nos | | |
| 9 | Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.15/16 amp switch | 10 | Nos | | |
| 10 | Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.5/6 amps switch | 25 | Nos | | |
| 11 | Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.15/16 amp switch | 25 | Nos | | |
| 12 | Supplying and fixing following modular switch/ socket on the existing modular plate & switch boxincluding connections but excluding modular plate etc. as required.6 pin 5/6 amp socket outlet | 25 | Nos | | |

Gross Total Cost:- Rs.....
.....(In words) We agree to supply the above goods in accordance
with the technical Specification for a total price of
Rs.....(amount
in figure)(amount in
words) with in the period specified in the invitation for quotation.

Signature of Quotationer