

No: 2582/2022/NK/TVPM

Office of the Nirmithi Kendra,  
B Block, 4th Floor, Civil Station,  
Kudappanakunnu, Thiruvananthapuram 43.  
Pmnirmithi01@gmail.com, 0471-2732929  
10.05.2022

**Quotation notice Oxygen pipe line Bridge work at SAT Trivandrum**

District Nirmithi Kendra invites Competitive quotation from authorized Suppliers/Individual in the form attached herewith for **Oxygen pipe line Bridge work at SAT Trivandrum.**

S.No.	PARTICULARS	QTY	UNIT
1	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil	10.866	CUM
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 nominal size)	1.391	CUM
3	Supplying & fixing GI section including all necessary provisions to whole supporting gas line all cost of labour, material hoisting, supporting charges etc complete.		
	25 X 25 X 2.6 mm Horizontal post including flat GI perpendicular bracings (45 cm length) at 50 cm interval. Including primer coat. Bridge work for pipe line using Rglr section 60X40X2.6 for Vertical post with required perpendicular bracings. Primer Coat.	97.5	Meter
	Horizontal at road crossings using flat GI 25X6mm including primer coat	42	Meter
4	Steel work in built up G I tubular ( round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete		
	ISMB 150	1047	Kg
	For bracings using ISA 40X40X5	158	Kg
	Gusset plate	85	Kg
5	Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and	242	Kg

	binding all complete upto plinth levelThermo Mechanically Treated bars of grade Fe-500D or more		
6	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. up tot floor five level excluding cost of centering, shuttering, finishing and reinforcement :1:1.5:3( 1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	4.603	CUM
7	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m.	7.8	CUM

## 2) Bid Price

- Quotationer shall be for the full quantity as described above. Corrections if any shall be made by crossing out re-writing with initial and date.
- The rate should be all inclusive of taxes, levies, transports etc. Usual deduction of taxes will be made from the gross amount of bill.
- The rate quoted by the bidder shall be fixed for the duration of the quotation and shall not be subject to adjustment on any account.
- The price should be quoted in Indian rupees only.

3) Each bidder shall submit only one tender.

## 4) Validity of quotation

. Quotation shall remain valid for a period not less than 45 days after the dead line date specified for submission

## 5) Evaluation of quotation

The quotationer will evaluate and compare the quotation determined to be substantially responsive ie which

- Are properly signed
- Confirm to the terms and conditions and specification.

## 6) Award of Quotation


a) The work will award to the quotationer whose quotation has been determined to be substantially responsive and who has offered the lowest evaluated quotation price

- The quotationer whose bid is accepted will be notified of the award of the contract by the purchaser prior to expiration of the quotation validity

period. The terms of the accepted offer shall be incorporated in the purchase order.

- 7) The amount will be released after verification of the material in physical, quality and receipt of invoice in this office according to the availability of funds. Individual or authorized dealers/agents are only eligible.
- 8) Quotationer are requested to provide your offer latest by 12 hours on **17.05.2022** and the quotation will be opened at **17.05.2022**.

We look forward to receiving your quotation and thank for your interest in this work.

  
**Project Manager**



### Format of Quotation

Sl No	Description	Quantity	Unit	Rate	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil	10.866	CUM		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 nominal size)	1.391	CUM		
3	Supplying & fixing GI section including all necessary provisions to whole supporting gas line all cost of labour, material hoisting, supporting charges etc complete.				
	25 X 25 X 2.6 mm Horizontal post including flat GI perpendicular bracings (45 cm length) at 50 cm interval. Including primer coat. Bridge work for pipe line using Rglr section 60X40X2.6 for Vertical post with required perpendicular bracings. Primer Coat.	97.5	Meter		
	Horizontal at road crossings using flat GI 25X6mm including primer coat	42	Meter		
4	Steel work in built up G I tubular ( round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting ,fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete				

	ISMB 150	1047	Kg		
	For bracings using ISA 40X40X5	158	Kg		
	Gusset plate	85	Kg		
5	Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Thermo Mechanically Treated bars of grade Fe-500D or more	242	Kg		
6	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. up to floor five level excluding cost of centering, shuttering, finishing and reinforcement :1:1.5:3( 1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	4.603	CUM		
7	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m.	7.8	CUM		

Gross Total Cost: - Rs.....

(In words) We agree to supply the above goods in accordance with the technical Specification for a total price of Rs.....(amount in figure).....(amount in words) with in the period specified in the invitation for tender.

**Signature of Quotationer**