

No: 1337(2)/2020/NK/TVPM

Office of the Nirmithi Kendra,
B Block, 4th Floor, Civil Station,
Kudappanakunnu, Thiruvananthapuram-43.
pnmirmithi01@gmail.com, 0471-2732929
16/09/2022

INVITATION OF TENDER

District Nirmithi Kendra invites Competitive quotation from authorized Firms/Experienced Individual in the form attached herewith for the work of **Construction of Compound Wall at Madavoor Village Office**

Sl. No.	DESCRIPTION	QTY	UNIT
1	Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-Charge. In cement mortar	4.801	cum
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil	14.70	cum
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 nominal size)	2.10	cum
4	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) up to plinth level with: Cement mortar 1:6 (1 cement : 6 coarse sand)	10.501	cum
5	Hollow block masonry using pre cast solid blocks (factory made) of size 40x20x10cm or nearest available size conforming to IS 2185 part I of 1979 for Super structure up to floor two level for 10 cm thick wall in: CM 1:6 (1 cement : 6 coarse sand) including cost of scaffolding etc complete	17.222	cum
6	15 mm cement plaster on rough side of single or half brick wall of mix: 1:6 (1 cement : 6 coarse sand)	261.60	sqm



7	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface:Water thinnable cement primer	261.60	sqm
8	Finishing walls with Acrylic Smooth exterior paint of required shade:New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	261.60	sqm
9	Item Shifted to head 14 as item 14,74Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	270.00	kg
10	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work	6	sqm

2) Bid Price

- The contract shall be for the full quantity as described above. Corrections if any shall be made by crossing out re-writing with initial and date.
- The rate should be all inclusive of taxes, levies, transports etc. Usual deduction of taxes will be made from the gross amount of bill.
- The rate quoted by the bidder shall be fixed for the duration of the contract and shall not be subject to adjustment on any account.
- The price should be quoted in Indian rupees only.

3) Each bidder shall submit only one quotation.

4) Validity of quotation

Tender shall remain valid for a period not less than 45 days after the dead line date specified for submission

5) Evaluation of quotation

The purchaser will evaluate and compare the tenders determined to be substantially responsive ie which

- Are properly signed
- Confirm to the terms and conditions and specification.



6) Award of Contract

- a) The purchaser will award the contract to the bidder whose quotation has been determined to be substantially responsive and who has offered the lowest evaluated tender price
- b) Notwithstanding above, the purchaser reserves the right to accept or reject any tenders and to cancel the bidding process and reject all quotation at anytime prior to the award of the contract
- c) The bidder whose bid is accepted will be notified of the award of the contract by the purchaser prior to expiration of the quotation validity period. The terms of the accepted offer shall be incorporated in the purchase order.
- 7) The amount will be released after verification of the material in physical, quality and receipt of invoice in this office according to the availability of funds. Individual or authorized dealers/agents are only eligible.
- 8) You are requested to provide your offer latest by 12 hours on **24.09.2022** and the Quotations will be opened at **24.09.2022**.

We look forward to receiving your quotation and thank for your interest in this work.


Project Manager



TENDER FORMAT

Sl No	Description	Qty	Unit	Rate	AMOUNT	
					Amount in figures	Amount in word
1	Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-Charge. In cement mortar	4.801	cum			
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil	14.70	cum			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 nominal size)	2.10	cum			
4	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) up to plinth level with: Cement mortar 1:6 (1 cement : 6 coarse sand)	10.501	cum			
5	Hollow block masonry using pre cast solid blocks (factory made) of size 40x20x10cm or nearest available size conforming to IS 2185 part I of 1979 for Super structure up to floor two level for 10 cm thick wall in: CM 1:6 (1 cement : 6 coarse sand) including cost of scaffolding etc complete	17.222	cum			
6	15 mm cement plaster on rough side of single or half brick wall of mix: 1:6 (1 cement : 6 coarse sand)	261.60	sqm			
7	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface: Water thinnable cement primer	261.60	sqm			
8	Finishing walls with Acrylic Smooth exterior paint of required shade: New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	261.60	sqm			



9	Item Shifted to head 14 as item 14.74Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	270.00	kg			
10	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work	6	sqm			

Gross Total Cost: - Rs.....

(In words) We agree to supply the above goods in accordance with the technical Specification for a total price of Rs.....(amount in figure).....(amount in words) with in the period specified in the invitation for tender.

Signature of Tenderer

