

No: 4310/22/NK/TVPM

Office of the Nirmithi Kendra,  
B Block, 4th Floor, Civil Station,  
Kudappanakunnu, Thiruvananthapuram 43.  
pmnirmithi01@gmail.com, 0471-2732929  
27/04/2023

**Invitation of Re- Quotation – Public Waiting area at Ottoor village office**


District Nirmithi Kendra invites Competitive quotation from authorized Suppliers/Individual in the form attached herewith for Construction works in District Nirmithi kendra's Project site- Public Waiting area at Ottoor village office

Sl. No	PARTICULARS	QTY	UNIT
1	Steel work in built up G I tubular ( round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete	517.805	M2
	80*40*2mm	104.16	Kg
	40*40*2mm	96.32	kg
	post	78.88	Kg
2	Providing and fixing precoated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+0.05%), total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length up to 12 meter or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling/self tapping screws of size (5.5x55mm) with EPDM seal, complete up to any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	20.16	sqm



*[Signature]*  
Executive Secretary  
District Nirmithi Kendra  
Thiruvananthapuram

3	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5m in width as well as 10 sqm on plan including disposal of excavated earth up to 50 m and lift up to 1.5 m, disposed soil to be levelled and neatly dressed: All Kinds of soil	3.480	cum
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:1/2:3 (cement : 11/2 coarse sand : 3 graded stone aggregate 20 mm nominal size)	0.180	cum
5	12 mm cement plaster of mix:1:4 ( 1 cement : 4 fine sand)	11	sqm
6	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required color & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge.60mm thick cement concrete paver block of M-35 grade with approved color, design& pattern.	11	sqm
<b>Gate work</b>			
1	tem Shifted to head 14 as item 14.74Steel work welded in built up sections/framed work, including Cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	266	kg
2	Painting on Steel work with synthetic enamel paint of approved brand and manufacture of required color to given an even shade: New work (two or more coats) including coat of approved steel primer but Excluding a coat of mordant solution.	15.2	sqm

  
Executive Secretary  
District Nirmithi Kendra  
Thiruvananthapuram



2) Bid Price

- a) Quotation on shall be for the full quantity as described above. Corrections if any shall be made by crossing out re-writing with initial and date.
  - b) The rate should be all inclusive of taxes, levies, transports etc. Usual deduction of taxes will be made from the gross amount of bill.
  - c) The rate quoted by the bidder shall be fixed for the duration of the contract and shall not be subject to adjustment on any account.
  - d) The price should be quoted in Indian rupees only.
- 3) Each bidder shall submit only one quotation

4) Validity of quotation

Quotation shall remain valid for a period not less than 45 days after the dead line date specified for submission

5) Evaluation of quotation

The quotation will evaluate and compare the quotation determined to be substantially responsive ie which

- a) Are properly signed
- b) Confirm to the terms and conditions and specification.

6) Award of quotation


- a) The work will award to the quotationer whose tender has been determined to be substantially responsive and who has offered the lowest evaluated quotation price
  - b) The quotationer whose bid is accepted will be notified of the award of the contract by the purchaser prior to expiration of the quotation validity period.
  - c) The terms of the accepted offer shall be incorporated in purchase order.
- 7) The amount will be released after verification of the material in physical, quality and receipt of invoice in this office according to the availability of funds. Individual or authorized dealers/agents are only eligible.
- 8) Quotationer are requested to provide your offer latest by 12 hours on 06/05/2023 and the quotation will be opened at 06/05/2023, 03.00pm

9) Cost of quotation form: Nil

10) Earnest Money deposit: Nil

We look forward to receiving your quotation and thank for your interest in this work.

Copy to: Website&Notice board

  
Executive Secretary



Format of quotation

File no: 4310/22/NK/TVPM- Public Waiting area at Ottoor village office

Sl No	Description	Quantity	Unit	Rate	AMOUNT	
					Amount in figures	Amount in words
1	Steel work in built up G I tubular ( round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete	517.805	M2			
	80*40*2mm	104.16	Kg			
	40*40*2mm	96.32	kg			
	post	78.88	Kg			
2	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+0.05%), total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling/self tapping screws of size (5.5x55mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces,	20.16	sqm			

*[Signature]*  
Executive Secretary  
District Nirmithi Kendra  
Thiruvananthapuram



	excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.					
3	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5m in width as well as 10 sqm on plan including disposal of excavated earth up to 50 m and lift up to 1.5 m, disposed soil to be levelled and neatly dressed:All Kinds of soil	3.480	cum			
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:1/2:3 (cement : 11/2 coarse sand : 3 graded stone aggregate 20 mm nominal size)	0.180	cum			
5	12 mm cement plaster of mix:1:4 ( 1 cement : 4 fine sand)	11	sqm			
6	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge. 60mm thick cement concrete paver block of M-35 grade with approved colour, design & pattern.	11	sqm			

*[Signature]*

Executive Secretary  
District Nirmithi Kendra  
Thiruvananthapuram




Gate work						
1	tem Shifted to head 14 as item 14.74 Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	266	kg			
2	Painting on Steel work with synthetic enamel paint of approved brand and manufacture of required colour to given an even shade: New work (two or more coats) including coat of approved steel primer but excluding a coat of mordant solution.	15.2	sqm			

Gross Total Cost: - Rs (In words) .....

We agree to supply the above goods in accordance with the technical Specification for a total price of Rs.....(amount in figure).....

(Amount in words) with in the period specified in the invitation for quotation.

  
Executive Secretary  
District Nirmithi Kendra  
Thiruvananthapuram

Signature of quotationer

