

No: 1304/2020/NK/TVPM

Office of the Nirmithi Kendra,
B Block, 4th Floor, Civil Station,
Kudappanakunnu, Thiruvananthapuram 43.
Pmnirmithi01@gmail.com, 0471-2732929
18.01.2021
2/.

QUOTATION NOTICE

QUOTATION NO.1304/20/DNK/3/21

The Project Manager, District Nirmithi Kendra, Thiruvananthapuram invites sealed quotations from the competent firms/experienced contractors in prescribed form for Networking and Air conditioning works at 3rd and 4th floor of Employment Exchange Office and Career Development Centre at Mini Civil station, Kadakampalli.

SI No	PARTICULARS	QTY	UNIT
I	Networking		
1.	supply and fixing 12 U hub rack with its all support accessories	2.00	Nos
2.	Supply and laying riser cable 10 pair in the existing channel / race way including numbering, connection /termination ,testing etc .As required	50.00	Mtr
3.	Supply of CAT 6 E Mounting cord - 3 Ft,gray (15 at switch end, 15 at used end and 5 extra as required by IT	40.00	Nos
4.	Supplying and fixing 20 pair crone connectors in suitable MS box with locking arrangement including termination of the riser cable, field side voice cable numbering tag etc	2.00	Nos
5.	Supply and termination of 24 port switch	10.00	Nos
6.	Supply & termination of Cat6 Fleximax Panel 24 Port (For Workstation Side Data)	10.00	Nos
7.	Supply & termination of RJ11 Type Information Outlet (For Voice)	25.00	Nos
8.	Supplying and laying of twisted single pair telephone cable for voice points in the existing PVC rigid pipe/race way cable tray including numbering for both end complete connection testing etc. As required	100.00	Nos
9.	Supply & termination of Giga speed Information Outlet, (For Data)	50.00	Nos
10.	Supplying and laying of Cat-6 E UTP cable in the existing PVC rigid pipe/race way cable tray including numbering for both end complete connection testing etc. as required	180.00	Mtr
11.	20mm Pvc conduit for 2 pair telephone cable laying	300.00	Mtr

12.	25mm PVC Conduit for Cat 6 utp cable laying	180.00	Mtr
13.	Supply and providing of BenQ/equivalent Projector with HDMI cable and power cable	1.00	Nos
14.	Supply of Podium Mic with Base	1.00	Nos
II	AIRCONDITIONER		
1.	Supply and laying of drain piping of PVC pipe from the indoor units to the nearest drain with 20 mm HardPVC pipe	30.00	Mtr
2.	Supply of necessary Copper refrigerant piping duly insulated with 6mm thick nitrile rubber tubinginsualtion with necessary fittings of following sizes.	25.00	Mtr
3.	SITC 1.5 TON SPLIT AC-Supply, installation, testing and commissioning of 1.5 T R, 3 star rated (as perBEE) Air Cooled High Wall mounted Inverter type Split Air Conditioner	1.00	Nos
4.	Supply and Installation of 2 ton Inverter split type 1 phase A/C including inbuilt stabilizer, outdoor unitclamp and accessories with following items. (make-Mitsubishi/daikin/LG/equivalent) 1] Hard drawncopper refrigerant piping with insulation- 3 mtr 2] Electrical cable b/w Indoor and outdoor units- 3 mtr 3]Insulated drain pipes - 3 mtr	4.00	Nos

Quotation forms and Quotation schedule may be downloaded from Nirmithi Kendra's Web site (www.dnktvpm.com)

1. Cover containing quotation should be addressed to the Member Secretary, Nirmithi Kendra Thiruvananthapuram, Civil Station.
2. Quotations are accepted through post or registered Couriers. Late quotations will not be accepted. Quotation will be opened in the presence of bidders or their authorized representatives who may be present at that time.
3. If the quotation date happens to be a declared holiday the quotation process will be done on the next working day at same time and place.
4. Further details can be had from the Office of Nirmithi Kendra in Thiruvananthapuram during working hours.


Project Manager

QUOTATION NO.1304/20/DNK/3/21
DISTRICT NIRMITHI KENDRA, THIRUVANANTHAPURAM
QUOTATION SCHEDULE

Sl.NO	PARTICULARS	QTY	UNIT	RATE	AMOUNT
I	Networking				
1.	Supply and fixing 12 U hub rack with its all support accessories	2.00	Nos		
2.	Supply and laying riser cable 10 pair in the existing channel / race way including numbering, connection /termination ,testing etc .As required	50.00	Mtr		
3.	Supply of CAT 6 E Mounting cord - 3 Ft,gray (15 at switch end, 15 at used end and 5 extra as required byIT	40.00	Nos		
4.	Supplying and fixing 20 pair crone connectors in suitable MS box with locking arrangement includingtermination of the riser cable, field side voice cable numbering tag etc	2.00	Nos		
5.	Supply and termination of 24 port switch	10.00	Nos		
6.	Supply & termination of Cat6 Fleximax Panel 24 Port (For Workstation Side Data)	10.00	Nos		
7.	Supply & termination of RJ11 Type Information Outlet (For Voice)	25.00	Nos		
8.	Supplying and laying of twisted single pair telephone cable for voice points in the existing PVC rigidpipe/race way cable tray including numbering for both end complete connection testing etc. Asrequired	100.00	Nos		
9.	Supply & termination of Giga speed Information Outlet, (For Data	50.00	Nos		
10.	Supplying and laying of Cat-6 E UTP cable in the existing PVC rigid pipe/race way cable tray includingnumbering for both end complete connection testing etc. as required	180.00	Mtr		
11.	20mm Pvc conduit for 2 pair telephone cable laying	300.00	Mtr		
12.	25mm PVC Conduit for Cat 6 utp cable laying	180.00	Mtr		
13.	Supply and providing of BenQ/equivalent Projector with HDMI cable and power cable	1.00	Nos		
14.	Supply of Podium Mic with Base	1.00	Nos		
II	AIRCONDITIONER				
1.	Supply and laying of drain piping of PVC pipe from the indoor units to the nearest drain with 20 mm HardPVC pipe	30.00	Mtr		

2.	Supply of necessary Copper refrigerant piping duly insulated with 6mm thick nitrile rubber tubinginsualtion with necessary fittings of following sizes.	25.00	Mtr		
3.	SITC 1.5 TON SPLIT AC-Supply, installation, testing and commissioning of 1.5 T R, 3 star rated (as perBEE) Air Cooled High Wall mounted Inverter type Split Air Conditioner	1.00	Nos		
4.	Supply and Installation of 2 ton Inverter split type 1 phase A/C including inbuilt stabilizer, outdoor unitclamp and accessories with following items.(make-Mitsubishi/daikin/LG/equivalent) 1] Hard drawn copper refrigerant piping with insulation- 3 mtr 2] Electrical cable b/w Indoor and outdoor units- 3 mtr 3]Insulated drain pipes - 3 mtr	4.00	Nos		
	TOTAL				
	GST,12%				

FIRM/ EXPERIENCED CONTRACTOR

PROJECT MANAGER

SIGN,

ADDRESS

QUOTATION NO.1304/20/DNK/1/21 DTD.22.01.2021

SPECIAL CONDITIONS

1. Offers not conforming to the specification given in the schedule and without the relevant documents will be rejected.
2. The rates should be quoted in the quotation schedule itself.
3. **The quotationer should sign in all the sheets attached with the quotation and quotation schedule including special conditions.**
4. Quotationer not satisfying the above special conditions is liable to be rejected without any further communication.
5. The work should be started within 7 days from the date of receipt of work order. Payment will be released from Nirmithi Kendra within 45 days of receiving the bill at office.
6. The undersigned reserves the right to reject any or all quotations without assigning any reasons.
7. Lower bidder has to execute an agreement in the prescribed format and 5% of the negotiated total amount shall be deposited to Nirmithi Kendra as security deposit on signing the agreement.
8. Penalty @ 0.1% per day for the total contract amount will be imposed for any delay in starting the work after 7 days of work order subject to a maximum of 10%. If the delay extends to such limits unbearable to Nirmithi Kendra, the order will be cancelled without further notice.
9. You are requested to provide your offer latest by 12 hours on **30.01.2021** and the Quotation will be opened at **30.01.2021**.


PROJECT MANAGER