

No: 1304/2020/NK/TVPM

Office of the Nirmithi Kendra,
B Block, 4th Floor, Civil Station,
Kudappanakunnu, Thiruvananthapuram 43.
Pmnirmithi01@gmail.com, 0471-2732929

18.01.2021

2/

QUOTATION NOTICE

QUOTATION NO.1304/20/DNK/1/21

The Project Manager, District Nirmithi Kendra, Thiruvananthapuram invites sealed quotations from the competent firms/experienced contractors in prescribed form for Interior works at 3rd and 4th floor of Employment Exchange Office and Career Development Centre at Mini Civil station, Kadakampalli.

| Sl.NO | PARTICULARS | QTY | UNIT |
|-------|--|--------|------|
| 1 | Modular Partition | | |
| | Supplying 75mm thick Modular partitions as per design and drawings. The frames are made out of powder coated approved shade aluminium sections with float glass panes of 4.0 mm thickness. 9mm thickness pre-laminated particle board tiles of approved shade fixed at the partitions as per the design and drawings bottom of the partition fixed with the single race way used for wiring purpose with end caps and hardware, provision for electrical cable tray below workstations including cost of all materials, transportation, labour charges, loading and unloading etc., complete | 190.80 | Sqm |
| 2. | Gypsum Board partition | | |
| | Providing and fixing Gypsum partition using GI stud frame work, skinning with 12.5mm gypsum board on both sides finished with jointing compound, paper tape, to give smooth surface finish up to one coat to top coat of primer etc., complete. | 270.00 | Sqm |
| 3. | Providing and fixing glazed partition using 10mm/12mm thick glass as per drawings, fixed in top & bottom with patch fitting. The rate includes the cost of all materials, lock, labour charges. Including for ceiling supporting Provision. | 40.00 | Sqm |
| 4. | Providing and fixing glazed partition using 12 mm thick toughened glass as per drawings, fixed in top & bottom with DORMA patch fitting. The rate includes the cost of all materials, lock, labour charges. | 50.00 | Sqm |
| 5. | Toughened Glass Door | | |

| | | | |
|-----|---|-------|-----|
| | Providing and fixing 12 mm thick frameless toughened glass door shutter of approved brand and manufacture, including providing and fixing top & bottom pivot & spring type fixing arrangement and making necessary holes etc. for fixing required door fittings, all complete as per direction of Engineer-in-charge (Door handle, lock and stopper etc to be paid separately) | 11.76 | Sqm |
| 6. | Providing and fixing aluminium extruded section body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 36 kg to 80 kg and door width from 701 mm to 1000 mm), with double speed adjustment with necessary accessories and screws etc. complete. | 4.00 | Nos |
| 7. | Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS: 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete. Twin rubber stopper | 4.00 | Nos |
| 8. | Providing and fixing bright finished 100 mm mortice lock with 6 levers without pair of handles of approved quality for aluminium door, with necessary screws etc complete as per direction of Engineer- in- charge | 4 | Nos |
| 9. | Providing and fixing bright /matt finished Stainless Steel handles of approved quality & make with necessary screws etc all complete. 125 mm | 5 | Nos |
| 10. | False Ceiling | | |
| | M/F Suspended ceiling, which includes Gypsteel® ULTRA CRP surface ribbed perimeter channels (having one flange of 20mm and another flange of 30mm and a web of 27mm) along the perimeter of ceiling, screw fixed to brick wall/partition with the help of nylon sleeves and screws, at 610mm centres. Then suspending Gypsteel® ULTRA CRP surface ribbed intermediate channels of size 45mm (with two flanges of 15mm each) from the soffit at 1220mm centres with Gypsteel ULTRA CRP surface ribbed ceiling angle of width 25mmx10mm fixed to soffit with GI cleat and steel expansion fasteners (Mfg by Saint Gobain Gyproc). Then Gypsteel® ULTRA CRP surface ribbed Ceiling section of having web of 51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to the Gypsteel® ULTRA intermediate channel with the help of connecting clip and in direction perpendicular to the Gypsteel® ULTRA intermediate channel at 457mm centres. Single layer of 12.5mm tapered edge Gyproc® MR (conforming to BS 1230 part 1) or Plain (conforming to IS 2095 part 1 1996) is then screw fixed to ceiling section with 25mm drywall screws at 230mm centres. Screw fixing is done mechanically either with screw driver or drilling machine with suitable attachment. Finally square and tapered edges of the boards are to be jointed and finished so as | 87 | Sqm |

| | | | |
|-----|--|-------|-----|
| | to have a flush look which includes filling and finishing with Gyproc Jointing compound, Gyproc Joint Paper tape and two coats of Drywall Top Coat (as per recommended practices of | | |
| 11. | Wall painting | | |
| | Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade. Two or more coats on new work | 450 | Sqm |
| 12. | Solid Doors | | |
| | SOLID DOORS Door frame 4" x 2" finished in flush door finished in laminate (1.0 mm) on both sides. Hardware - Door closer with standard arm. Door hinge - 4"x3" x 3 mm, Clear glass (6 mm thk.) for vision panel as per given dwg. S.S. Handles as shown in dwg. S.S. Handles with lock. size: 2100x900 | 8 | Nos |
| 13. | Wooden panelling | | |
| | Wooden Wall Paneling (Reception area) Supplying, providing and fixing in position Wooden wallpanelling using with 19 mm thick marine plywood on the finished face and finished with 1mm lamination approved brand and shade as in the design drawing including cost conveyance of all materials, labour charges loading and unloading etc. complete. | 30 | Sqm |
| 14. | Acquastic Double Skin Glazed Partition | | |
| | Acquastic Double Skin Glazed Partition Providing & Fixing of Acquastic Glass Gypsum Partition using Framework for 70mm Stud (0.5mm Thick Flange of 34mm and other Flange of 36mm made of GI steel) Placed at 600mm Center to Center in 72mm Floor and Ceiling Channel. (0.5mm thick Flange equal plant of 32mm made of GI steel). It is anchored to the floor and ture Ceiling into suitable angle Fasteners or metal Screws with Nylon Plug 12.5mm Thick Gypsum board are to be fixed to the frame work with joints staggered to avoid leakage to Joints. Existing GI Frame work using Star screw every 300mm center to center. Partition door area all around for inside the frame using Hard wood. The Partition inside 25mm glass wool the Part inside using 25mm Thick glass wool of density of 16kg per m3 shall be based in the Kavity. Finally square and paper edge of the post or to be joined and finished so as to have a fresh look includes Beading and finishing Gyp work Jointing Compound gypwork jointing Paper Tape and one coat of Dry wall Top Coat. if Necessary Area 5mm plain glass are Fixed | 80 | Sqm |
| 15. | Printed stickers/etching sticker | 17.28 | Sqm |
| 16. | Office Inside Name Signage Supply and fixing charge | 40 | Nos |
| 17. | Outside Signage | 4 | Nos |

| | | | |
|-----|--|-------|-----|
| 18. | Supply and Fixing of Main Signage | 2 | Nos |
| 19. | Providing and Fixing of vertical Blinds 100mm wide with washable fabric ,Indian Track Type | 38.88 | Sqm |

Quotation forms and Quotation schedule may be downloaded from Nirmithi Kendra's Web site (www.dnktvpm.com)

1. Cover containing quotation should be addressed to the Member Secretary, Nirmithi Kendra Thiruvananthapuram, Civil Station.
2. Quotations are accepted through post or registered Couriers. Late quotations will not be accepted. Quotation will be opened in the presence of bidders or their authorized representatives who may be present at that time.
3. If the quotation date happens to be a declared holiday the quotation process will be done on the next working day at same time and place.
4. Further details can be had from the Office of Nirmithi Kendra in Thiruvananthapuram during working hours.


Project Manager

QUOTATION NO.1304/20/DNK/1/21

DISTRICT NIRMITHI KENDRA, THIRUVANANTHAPURAM

QUOTATION SCHEDULE


| Sl.NO | PARTICULARS | QTY | UNIT | RATE | AMOUNT |
|-------|--|--------|------|------|--------|
| 1 | Modular Partition | | | | |
| | Supplying 75mm thick Modular partitions as per design and drawings. The frames are made out of powder coated approved shade aluminium sections with float glass panes of 4.0 mm thickness. 9mm thickness pre-laminated particle board tiles of approved shade fixed at the partitions as per the design and drawings bottom of the partition fixed with the single race way used for wiring purpose with end caps and hardware, provision for electrical cable tray below workstations including cost of all materials, transportation, labour charges, loading and unloading etc., complete | 190.80 | Sqm | | |
| 2. | Gypsum Board partition | | | | |
| | Providing and fixing Gypsum partition using GI stud frame work, skinning with 12.5mm gypsum board on both sides finished with jointing compound, paper tape, to give smooth surface finish up to one coat to top coat of primer etc., complete. | 270.00 | Sqm | | |
| 3. | Providing and fixing glazed partition using 10mm/12mm thick glass as per drawings, fixed in top & bottom with patch fitting. The rate includes the cost of all materials, lock, labour charges. Including for ceiling supporting Provision. | 40.00 | Sqm | | |
| 4. | Providing and fixing glazed partition using 12 mm thick toughened glass as per drawings, fixed in top & bottom with DORMA patch fitting. The rate includes the cost of all materials, lock, labour charges. | 50.00 | Sqm | | |
| 5. | Toughened Glass Door | | | | |
| | Providing and fixing 12 mm thick frameless toughened glass door shutter of approved brand and manufacture, including providing and fixing top & bottom pivot & spring type fixing arrangement and making necessary holes etc. for fixing required door fittings, all complete as per direction of Engineer-in-charge (Door handle, lock and stopper etc to be paid separately) | 11.76 | Sqm | | |

| | | | | | |
|-----|--|------|-----|--|--|
| 6. | Providing and fixing aluminium extruded section body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 36 kg to 80 kg and door width from 701 mm to 1000 mm), with double speed adjustment with necessary accessories and screws etc. complete. | 4.00 | Nos | | |
| 7. | Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS: 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete. Twin rubber stopper | 4.00 | Nos | | |
| 8. | Providing and fixing bright finished 100 mm mortice lock with 6 levers without pair of handles of approved quality for aluminium door, with necessary screws etc. complete as per direction of Engineer-in-charge | 4 | Nos | | |
| 9. | Providing and fixing bright /matt finished Stainless Steel handles of approved quality & make with necessary screws etc. all complete. 125 mm | 5 | Nos | | |
| 10. | False Ceiling | | | | |
| | M/F Suspended ceiling, which includes Gypsteel® ULTRA CRP surface ribbed perimeter channels (having one flange of 20mm and another flange of 30mm and a web of 27mm) along the perimeter of ceiling, screw fixed to brick wall/partition with the help of nylon sleeves and screws, at 610mm centres. Then suspending Gypsteel® ULTRA CRP surface ribbed intermediate channels of size 45mm (with two flanges of 15mm each) from the soffit at 1220mm centres with Gypsteel ULTRA CRP surface ribbed ceiling angle of width 25mmx10mm fixed to soffit with GI cleat and steel expansion fasteners (Mfg by Saint Gobain Gyproc). Then Gypsteel® ULTRA CRP surface ribbed Ceiling section of having web of 51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to the Gypsteel® ULTRA intermediate channel with the help of connecting clip and in direction perpendicular to the Gypsteel® ULTRA intermediate channel at 457mm centres. Single layer of 12.5mm tapered edge Gyproc® MR (conforming to BS 1230 part 1) or Plain (conforming to IS 2095 part 1 1996) is then screw fixed to ceiling section with 25mm drywall screws at 230mm centres. Screw fixing is done mechanically either with screw | 87 | Sqm | | |

| | | | | | |
|-----|--|-----|-----|--|--|
| | driver or drilling machine with suitable attachment. Finally square and tapered edges of the boards are to be jointed and finished so as to have a flush look which includes filling and finishing with Gyproc Jointing compound, Gyproc Joint Paper tape and two coats of Drywall Top Coat (as per recommended practices of | | | | |
| 11. | Wall painting | | | | |
| | Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade: Two or more coats on new work | 450 | Sqm | | |
| 12. | Solid Doors | | | | |
| | SOLID DOORS Door frame 4" x 2" finished in flush door finished in laminate (1.0 mm) on both sides. Hardware - Door closer with standard arm. Door hinge - 4"x3" x 3 mm, Clear glass (6 mm thk.) for vision panel as per given dwg. S.S. Handles as shown in dwg. S.S. Handles with lock. size: 2100x900 | 8 | Nos | | |
| 13. | Wooden panelling | | | | |
| | Wooden Wall Paneling (Reception area) Supplying, providing and fixing in position Wooden wallpanelling using with 19 mm thick marine plywood on the finished face and finished with 1mm lamination approved brand and shade as in the design drawing including cost conveyance of all materials, labour charges loading and unloading etc. complete. | 30 | Sqm | | |
| 14. | Acquastic Double Skin Glazed Partition | | | | |
| | Acquastic Double Skin Glazed Partition Providing & Fixing of Acquastic Glass Gypsum Partition using Framework for 70mm Stud (0.5mm Thick Flange of 34mm and other Flange of 36mm made of GI steel) Placed at 600mm Center to Center in 72mm Floor and Ceiling Channel. (0.5mm thick Flange equal plant of 32mm made of GI steel). It is anchored to the floor and ture Ceiling into suitable anger Fastners or metal Screws with Nylon Plug 12.5mm Thick Gypsum board are to be fixed to the frame work with joints staggered avoid leakage to Joints. Existing GI Frame work using Star screw every 300mm center to center. Partition door area all around for inside the frame using Hard wood. The Partition inside 25mm glass wool the Part inside | 80 | Sqm | | |

| | | | | | |
|-----|---|-------|-----|--|--|
| | using 25mm Thick glass wool of density of 16kg per m3 shall we based in theKavity. Finally square and paper edge of the post or to be joined and finished so as to have a fresh lookincludes Beading and finishing Gyp work Jointing Compound gypwork jointing Paper Tape and one coatof try wall Top Coat. if Necessary Area 5mm plain glass are Fixed | | | | |
| 15. | Printed stickers/etching sticker | 17.28 | Sqm | | |
| 16. | Office Inside Name Signage Supply and fixing charge | 40 | Nos | | |
| 17. | Outside Signage | 4 | Nos | | |
| 18. | Supply and Fixing of Main Signage | 2 | Nos | | |
| 19. | Providing and Fixing of vertical Blinds 100mm wide with washable fabric ,Indian Track Type | 38.88 | Sqm | | |
| | TOTAL | | | | |
| | GST 12% | | | | |
| | GRAND TOTAL | | | | |

FIRM/ EXPERIENCED CONTRACTOR


PROJECT MANAGER

SIGN,

ADDRESS

QUOTATION NO.1304/20/DNK/1/21 DTD.22.01.2021

SPECIAL CONDITIONS

1. Offers not conforming to the specification given in the schedule and without the relevant documents will be rejected.
2. The rates should be quoted in the quotation schedule itself.
3. **The quotationer should sign in all the sheets attached with the quotation and quotation schedule including special conditions.**
4. Quotationer not satisfying the above special conditions is liable to be rejected without any further communication.
5. The work should be started within 7 days from the date of receipt of work order. Payment will be released from Nirmithi Kendra within 45 days of receiving the bill at office.
6. The undersigned reserves the right to reject any or all quotations without assigning any reasons.
7. Lower bidder has to execute an agreement in the prescribed format and 5% of the negotiated total amount shall be deposited to Nirmithi Kendra as security deposit on signing the agreement.
8. Penalty @ 0.1% per day for the total contract amount will be imposed for any delay in starting the work after 7 days of work order subject to a maximum of 10%. If the delay extends to such limits unbearable to Nirmithi Kendra, the order will be cancelled without further notice.
9. You are requested to provide your offer latest by 12 hours on **30.01.2021** and the Quotation will be opened at **30.01.2021**.


PROJECT MANAGER