

No: 1557/2020/NK/TVPM

Office of the Nirmithi Kendra,  
B Block, 4th Floor, Civil Station,  
Kudappanakunnu, Thiruvananthapuram 43.  
Pmnirmithi01@gmail.com, 0471-2732929  
06/02/2021

**Quotation notice for Electrical works for Setting up of Nine bedded ICU at Neyyattinkara Geneneral Hospital**

District Nirmithi Kendra invites Competitive quotations from authorized Firms/Experienced individual in the form attached herewith for Electrical works for Setting up of Nine bedded ICU at Neyyattinkara Geneneral Hospital, Thiruvananthapuram.

S.No.	PARTICULARS	QTY	UNIT
1	Supply and drawing of two runs of 1.5 sq mm FRLS PVC insulated single core stranded copper wires of 650/1100V grade along with one run of 1.5 sq mm FRLS PVC insulated green continuous copper earth wire for continuous earthing through existing conduit.	20	m
2	Supply and drawing of two runs of 2.5 sq mm FRLS PVC insulated single core stranded copper wires along with one run of 2.5 sq mm FRLS PVC insulated green copper earth wire for continuous earthing through the existing conduit.	200	m
3	Supply and drawing of two runs of 4 sq mm FRLS PVC insulated single core stranded copper wires along with one run of 4 sq mm FRLS PVC insulated green copper earth wire for continuous earthing through the existing conduit.	30	m
4	Supply and drawing of two runs of 6sq mm FRLS PVC insulated single core stranded copper wires along with one run of 6 sq mm FRLS PVC insulated green copper earth wire for continuous earthing through the existing conduit.	30	m
5	Supplying and fixing 20 mm medium class PVC conduit along with the required accessories in concrete / surface / recess including cutting the wall and making good the same in case of recessed conduit as required	300	m



6	Supplying and 16 switch with indicator including PVC box alongwith modular base & cover plate etc	2	no
7	Supplying and 16A amp socket outlet including PVC box alongwith modular base & cover plate etc..	2	no
8	Supply and installation of SPN 12Way MCB DB for 1 phase inclusive of copper / brass bus bar, neutral link and DIN bar suitable for incorporating MCB isolator etc. including providing blanking plates in the blanking slots and fixed in recess including cutting holes on the wall, making good the damages, colour washing etc as required Incomer40A 30mA RCCB-1No, Outgoings-6/10/16 SP MCBs-8 Nos [For UPS & RA Power]	2	no
9	Supply and Installation of wall mounted 4 feet bed head panel including wiring with two runs of 2.5 sq mm FRLS PVC insulated single core stranded copper wires along with one run of 2.5 sq mm FRLS PVC insulated green copper earth wire for continuous earthing through 20mm pvc conduit [25 mtr circuit] and following accessories. 1- 5/6 Amps switch-1 no 2- 3 pin 5/6 Amp socket outlet-1 no 3-15/16 Amps switch-5 no 4-6pin 15/16 Amps (universal) socket outlet-5no 5-Telephone socket outlet-1 no 6-RJ45 Keystone IO jack with cover and face plate 7- IV Stand. 8-Monitor stand wall mounted. 9-Ward vacuum unit clip. 10-Provision Gas/Vacuum outlets as follows:- a] One oxygen outlet. b] One Vacuum outlet. c] One Compressed Air outlet 4 Bar. d] One Nitrous outlet	9	nos

## 2) Bid Price

- The contract shall be for the full quantity as described above. Corrections if any shall be made by crossing out re-writing with initial and date.
- The rate should be all inclusive of taxes, levies, transports, Unloading etc.
- Usual deduction of taxes will be made from the gross amount of bill.
- The rate quoted by the bidder shall be fixed for the duration of the contract and shall not be subject to adjustment on any account.
- The price should be quoted in Indian rupees only.



3) Each bidder shall submit only one quotation.

4) Validity of quotation

Quotation shall remain valid for a period not less than 45 days after the dead line date specified for submission

5) Evaluation of quotation

The purchaser will evaluate and compare the quotations determined to be substantially responsive ie which

- a) Are properly signed
- b) Confirm to the terms and conditions and specification.

6) Award of Contract

- a) The purchaser will award the contract to the bidder whose quotations has been determined to be substantially responsive and who has offered the lowest evaluated quotation price
- b) Notwithstanding above, the purchaser reserves the right to accept or reject any quotations and to cancel the bidding process and reject all quotations at any time prior to the award of the contract
- c) The bidder whose bid is accepted will be notified of the award of the contract by the purchaser prior to expiration of the quotation validity period.

The terms of the accepted offer shall be incorporated in the purchase order.

7) The amount will be released after verification of the material in physical ,quality and receipt of invoice in this office according to the availability of funds. Individual or authorized dealers/agents are only eligible.

8) You are requested to provide your offer latest by 12 hours on **12.02.2021** and the quotation will be opend at **12.02.2021**.

We look forward to receiving your quotations and thank for your interest in this work.



  
**Project Manager**

**Format of Quotation**

Sl No	Description	Quantity	Unit	Rate	AMOUNT	
					Amount in figures	Amount in words
1	Supply and drawing of two runs of 1.5 sq mm FRLS PVC insulated single core stranded copper wires of 650/1100V grade along with one run of 1.5 sq mm FRLS PVC insulated green continuous copper earth wire for continuous earthing through existing conduit.	20	m			
2	Supply and drawing of two runs of 2.5 sq mm FRLS PVC insulated single core stranded copper wires along with one run of 2.5 sq mm FRLS PVC insulated green copper earth wire for continuous earthing through the existing conduit.	200	m			
3	Supply and drawing of two runs of 4 sq mm FRLS PVC insulated single core stranded copper wires along with one run of 4 sq mm FRLS PVC insulated green copper earth wire for continuous earthing through the existing conduit.	30	m			

4	Supply and drawing of two runs of 6sq mm FRLS PVC insulated single core stranded copper wires along with one run of 6 sq mm FRLS PVC insulated green copper earth wire for continuous earthing through the existing conduit.	30	m			
5	Supplying and fixing 20 mm medium class PVC conduit along with the required accessories in concrete / surface / recess including cutting the wall and making good the same in case of recessed conduit as required	300	m			
6	Supplying and 16 switch with indicator including PVC box alongwith modular base & cover plate etc	2	no			
7	Supplying and 16A amp socket outlet including PVC box alongwith modular base & cover plate etc..	2	no			
8	Supply and installation of SPN 12Way MCB DB for 1 phase inclusive of copper / brass bus bar, neutral link and DIN bar suitable for incorporating MCB isolator etc. including providing blanking plates in the blanking slots and fixed in recess including cutting holes on the wall, making good the damages, colour washing etc as required Incomer40A 30mA RCCB-1No, Outgoings- 6/10/16 SP MCBs-8 Nos [For UPS & RA Power]	2	no			
9	Supply and Installation of wall mounted 4 feet bed head panel including wiring with two runs of 2.5 sq mm FRLS PVC insulated single core stranded copper wires along with one run of 2.5 sq mm FRLS PVC insulated green copper earth wire for continuous earthing through 20mm pvc conduit [25 mtr circuit] and	9	nos			



following accessories. 1-5/6 Amps switch-1 no 2- 3 pin 5/6 Amp socket outlet-1 no 3-15/16 Amps switch-5 no 4-6pin 15/16 Amps (universal) socket outlet-5no 5-Telephone socket outlet-1 no 6-RJ45 Keystone IO jack with cover and face plate 7- IV Stand. 8-Monitor stand wall mounted. 9-Ward vacuum unit clip. 10-Provision Gas/Vacuum outlets as follows:- a) One oxygen outlet. b) One Vacuum outlet. c) One Compressed Air outlet 4 Bar. d) One Nitrous outlet					
--	--	--	--	--	--

Gross Total Cost: - Rs.....

(In words) We agree to supply the above goods in accordance with the technical Specification for a total price of Rs.....(amount in figure).....(amount in words) with in the period specified in the invitation for quotation.

**Signature of Contractor**