

No: 1086(4)/2020/NK/TVPM

Office of the Nirmithi Kendra,
B Block, 4th Floor, Civil Station,
Kudappanakunnu, Thiruvananthapuram 43.
Pmnirmithi01@gmail.com, 0471-2732929
25.02.2021

QUOTATION NOTICE

The Project Manager, District Nirmithi Kendra, Thiruvananthapuram invites sealed quotations from the competent firms/experienced contractors in prescribed form for Renovation of damaged road at Nandhamkuzhi Uruttuvila Kshetram Road.

Sl No	PARTICULARS	QTY	UNIT
1	Restoration of rain cuts with soil, moorum, gravel or a mixture of these, clearing the loose soil, benching for 300 mm width, laying fresh material in layers not exceeding 250 mm and compacting with plate compactor or power rammers to restore the original alignment, levels and slopes	20	cum
2	Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 503, back filling the pot holes with hot bituminous material as per clause 511, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 Filling Pot-holes and Patch Repairs with open-Graded Premix surfacing, 20mm	900	sqm
3	Filling Pot-holes and Patch Repairs with Bituminous concrete, 40mm. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 503, back filling the pot holes with hot bituminous material as per clause 504, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 - For grading I Material	900	sqm
4	Construction of granular sub-base by providing graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. Grading-III -For lower sub base - Mix in Place Method	82.08	cum



5	Providing and laying bituminous concrete with 80-100 TPH hot mix plant producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder (NRMB) @ 5.4 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 507 complete in all respects Grading - II (13.2 mm Nominal Size)	25.84	cum
6	Applying crusher dust to areas of road where bleeding of excess bitumen has occurred Dusting	25.84	sqm

2) Bid Price

- The contract shall be for the full quantity as described above. Corrections if any shall be made by crossing out re-writing with initial and date.
- The rate should be all inclusive of taxes, levies, transports etc.
- Usual deduction of taxes will be made from the gross amount of bill.
- The rate quoted by the bidder shall be fixed for the duration of the contract and shall not be subject to adjustment on any account.
- The price should be quoted in Indian rupees only.

3) Each bidder shall submit only one quotation.

4) Validity of quotation

Quotation shall remain valid for a period not less than 45 days after the dead line date specified for submission

5) Evaluation of quotation

The purchaser will evaluate and compare the quotations determined to be substantially responsive i.e., which

- a) Are properly signed
- b) Confirm to the terms and conditions and specification.

6) Award of Contract

- a) The purchaser will award the contract to the bidder whose quotations has been determined to be substantially responsive and who has offered the lowest evaluated quotation price
- b) Notwithstanding above, the purchaser reserves the right to accept or reject any quotations and to cancel the bidding process and reject all quotations at anytime prior to the award of the contract
- c) The bidder whose bid is accepted will be notified of the award of the contract by the purchaser prior to expiration of the quotation validity period. The terms of the accepted offer shall be incorporated in the purchase order.

7) The amount will be released after verification of the material in physical, quality and receipt of invoice in this office according to the availability of funds. Individual or Authorized dealers/agents are only eligible.

8) You are requested to provide your offer latest by 12 hours on **05.03.2021** and the Quotation will be opened at **05.03.2021**.

We look forward to receiving your quotations and thank for your interest in this work.



Project Manager



QUOTATION NO.1086(4)/20/DNK**DISTRICT NIRMITHI KENDRA, THIRUVANANTHAPURAM****QUOTATION SCHEDULE**

Sl.NO	PARTICULARS	QTY	UNIT	RATE	AMOUNT
1	Restoration of rain cuts with soil, moorum, gravel or a mixture of these, clearing the loose soil, benching for 300 mm width, laying fresh material in layers not exceeding 250 mm and compacting with plate compactor or power rammers to restore the original alignment, levels and slopes	20	cum		
2	Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 503, back filling the pot holes with hot bituminous material as per clause 511, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 Filling Pot-holes and Patch Repairs with open-Graded Premix surfacing, 20mm	900	sqm		
3	Filling Pot-holes and Patch Repairs with Bituminous concrete, 40mm. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 503, back filling the pot holes with hot bituminous material as per clause 504, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 - For grading I Material	900	sqm		
4	Construction of granular sub-base by providing graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. Grading-III -For lower sub base - Mix in Place Method	82.08	cum		
5	Providing and laying bituminous concrete with 80-100 TPH hot mix plant producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder(NRMB) @ 5.4 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 507 complete in all respectsGrading - II (13.2 mm Nominal Size)	25.84	cum		
6	Applying crusher dust to areas of road where bleeding of excess bitumen has occurred Dusting	25.84	sqm		

		TOTAL				
--	--	--------------	--	--	--	--

Gross Total Cost:- Rs.....
(In words) We agree to supply the above goods in accordance
 with the technical Specification for a total price of
 Rs.....(amount
 in figure)(amount in
 words) with in the period specified in the invitation for quotation.

Signature of Quotationer