

No: 1770/2020/NK/TVPM

Office of the Nirmithi Kendra,
B Block, 4th Floor, Civil Station,
Kudappanakunnu, Thiruvananthapuram 43.
Pmnirmithi01@gmail.com, 0471-2732929
25/05/2021

Quotation notice for Setting up of Waiting area in Medical College Hospital, Thiruvananthapuram

District Nirmithi Kendra invites Competitive quotations from authorized Firms/Experienced individual in the form attached herewith for Setting up of Waiting area in Medical College Hospital, Thiruvananthapuram.

S.No.	PARTICULARS	QTY	UNIT
1	Fabricating& erecting posts with 60*40*2mm including cost of materials painting with synthetic enamel paint two coat including all charges etc complete., V e r t i c a l p o s t (6 0 x 4 0 x 2 . 2 m m)	120.96	Kg
2	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. 5 mm thick plate for fixing post	55.02	Kg
3	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete		
	Rafter(60x40x2.2mm)	378.43	Kg
	Purlin(25x25x2.6mm)	106.47	Kg
7	Providing Trafford Aluminium sheet roofing including vertical/ curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal / vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 1.00 mm thick with zinc coating not less than 275 gm/m2	110.25	Sqm

8	Providing and fixing hard drawn steel wire fabric of size 75 x25 mm mesh or other suitable size wire mesh to be fixed & firmly anchored to the concrete surface by means of "L" shaped mild steel shear key welded with existing reinforcement including the cost of materials, labour, tool & plants as approved by Engineer	75.04	Sqm
9	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	0.63	Cum

2) Bid Price

- The contract shall be for the full quantity as described above. Corrections if any shall be made by crossing out re-writing with initial and date.
- The rate should be all inclusive of taxes, levies, transports, Unloading etc.
- Usual deduction of taxes will be made from the gross amount of bill.
- The rate quoted by the bidder shall be fixed for the duration of the contract and shall not be subject to adjustment on any account.
- The price should be quoted in Indian rupees only.

3) Each bidder shall submit only one quotation.

4) Validity of quotation

- Quotation shall remain valid for a period not less than 45 days after the dead line date specified for submission

5) Evaluation of quotation

The purchaser will evaluate and compare the quotations determined to be substantially responsive ie which


- Are properly signed
- Confirm to the terms and conditions and specification.

6) Award of Contract

- The purchaser will award the contract to the bidder whose quotations has been determined to be substantially responsive and who has offered the lowest evaluated quotation price

- b) Notwithstanding above, the purchaser reserves the right to accept or reject any quotations and to cancel the bidding process and reject all quotations at any time prior to the award of the contract
 - c) The bidder whose bid is accepted will be notified of the award of the contract by the purchaser prior to expiration of the quotation validity period.
The terms of the accepted offer shall be incorporated in the purchase order.
- 7) The amount will be released after verification of the material in physical, quality and receipt of invoice in this office according to the availability of funds. Individual or authorized dealers/agents are only eligible.
- 8) You are requested to provide your offer latest by 12 hours on **31.05.2021** and the quotation will be opened at **31.05.2021**.

We look forward to receiving your quotations and thank for your interest in this work.

Handwritten signature in blue ink, followed by a horizontal line and the date 25.05.2021.

Project Manager

Foramat of Ouotation

Sl No	Description	Quantity	Unit	Rate	AMOUNT	
					Amount in figures	Amount in words
1	Fabricating& erecting posts with 60*40*2mm including cost of materials painting with synthetic enamel paint two coat including all charges etc complete., Vertical Post (60x40x2mm)	120.96	Kg			
2	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. 5 mm thick plate for fixing post	55.02	Kg			
3	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete					
	Rafter(60x40x2.2mm)	378.43	Kg			
	Purlin(25x25x2.6mm)	106.47	Kg			
7	Providing Trafford Aluminium sheet roofing including vertical/ curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal / vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 1.00 mm thick with zinc coating	110.25	Sqm			

	not less than 275 gm/m2					
8	Providing and fixing hard drawn steel wire fabric of size 75 x25 mm mesh or other suitable size wire mesh to be fixed & firmly anchored to the concrete surface by means of "L" shaped mild steel shear key welded with existing reinforcement including the cost of materials, labour, tool & plants as approved by Engineer	75.04	Sqm			
9	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	0.63	Cum			

Gross Total Cost: - Rs.....

(In words) We agree to supply the above goods in accordance with the technical Specification for a total price of Rs.....(amount in figure).....(amount in words) with in the period specified in the invitation for quotation.

Signature of Contractor